BILL OF QUANTITIES

ICF KIT · CONCRETE · LABOUR

CLIFTON COLLEGE GARAGE SITE, CLIFTON PARK ROAD

Detached House (GF + 1F + 2F in the roof) · Clifton Park Road, Clifton, Bristol · ENGLAND

Quotation Reference	ES26-065
Project	Clifton College Garage Site, Clifton Park Road
House Type	Detached house: 6in XR35 FB (Brick Ledge) + GF / 1F / 2F with parapet gables, oriel + bay in ICF, metal-web joist floors, cut roofs C24, stone / ashlar outer leaf by others
Client	Cuckfield Real Estate Ltd
Site Address	Clifton College Garage Site, Clifton Park Road, Clifton, Bristol
BOQ Issued	02 November 2026
BOQ Reference	BOQ-ES26-065-001
Prepared by	Tom Smith — BuildEase Manager, Nudura UK
Issued by	Tremco Construction Products Group
Currency	Pound Sterling (GBP) · VAT at 20%
Measurement Convention	RICS New Rules of Measurement (NRM2)

IMPORTANT NOTICE — DISCLAIMER

- This Bill of Quantities is supplied in good faith based on the BuildEase take-off models for Clifton College Garage Site, Clifton Park Road and the associated Tremco CPG quotation.
- ALL QUANTITIES SHOULD BE INDEPENDENTLY CHECKED AND VERIFIED BY THE PROJECT QS / QUANTITY SURVEYOR before tender submission, ordering or contract award.
- This BOQ does NOT include an external render / finish allowance. Any render, coatings or external wall finish must be measured and priced separately.
- Section C (Concrete) volumes are geometric voids — allow ~3% web displacement deduction and ~5% wastage on top when ordering ready-mix.
- Section D (Labour) day estimates are scaled proportionately from a reference project; actual gang productivity will vary with site conditions, weather and trade experience.
- BuildEase, Tremco Construction Products Group and Nudura UK accept no liability for tender or contract outcomes arising from the use of these figures. If in doubt — ask.
- Contact: Tom Smith — BuildEase Manager, Nudura UK — for clarification on any quantity or rate basis in this document.

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. Building height: the 2F (rooms in the roof) FFL is 5,800 above the GF FFL, ~5.95 m above the lowest adjoining ground (ADB Diagram D6, ground ASSUMED ~150 below GF FFL - to be confirmed on a measured survey); the main gable parapet apex is ~10.22 m above GF FFL (~10.4 m above ground) - BELOW 11 m on either measure, so the 11-18 m fire band does not apply. One detached dwelling, 3 storeys (GF / 1F / 2F in the roof) - within the LABC Warranty 3-storey limit for ICF (warranty provider to confirm); Consequence Class 1 house (Approved Document A).

NOT FOR CONSTRUCTION. The GF "floor" slot of the programme is the ground-bearing slab by others; slab concrete, rebar and pumping are NOT in this ICF BOQ (coordination quantities in the finishes package Bill 6). Engineer to design: the indicative steels SB1-SB4 (UB 356 x 171 x 51) carrying the 1F / 2F walls over the GF open plan, the oriel RC corbel / steel, the masonry support of the stone outer leaf above the Brick Ledge, the cross-gable valleys over the main slope and the strip footing.

CONTENTS

Section	Description	Sheet	Status	
	Cover & Project Information	**Cover**		
	Contents	**Contents**		
	Indicative Programme (Gantt)	**Programme**	*Information*	
	Summary of Tender Pricing	**Summary**		
A	Preliminaries	**A_Preliminaries**	*Contractor priced*	
B	ICF Kit Supply	**B_ICF_Supply**	*Pre-priced*	
C	Concrete Supply, Pump & Placement	**C_Concrete**	*Contractor priced*	
D	Labour — ICF, Floors & Roofs	**D_Labour**	*Contractor priced*	
F	Reference Data (informative only)	**F_Reference**	—	

PROG · INDICATIVE INSTALL PROGRAMME — RESOURCE-LEVELLED, ONE COLUMN PER WORKING DAY

Group-by-group sequential build with a staggered start between groups. ICF install + snag + pour cycles, intermediate floors and roof structure are completed before moving on. Resourcing and durations below are indicative and must be validated by site management. Render / external finish is NOT included in this programme.

Group	Plots	Forms	Weeks	Start wk
Clifton Park Road	1	309	5	1



LEGEND

	ICF walls — first lift: FB foundation incl. the Brick Ledge course (erection, snag & pour)
	ICF walls — L1 (after the GF slab), L2 (after the 1F floor), L3 incl. the parapet gables (after the 2F floor)
	Concrete pour — sized at 60 m3 per pump-day, ICF crew attends, pump on site
	Curing — pours held to Fridays where possible so the 2 curing days fall on the weekend; a mid-week pour cures 2 working days
	Floor slots — GF slab (by others) after FB, 1F floor after L1, 2F floor after L2 (1 day each - one plot)
	Roof structure (cut roofs, main + wing B + oriel), 1 day - one plot

RESOURCING

• 1 ICF crews of 8 trained installers (each crew = 2 four-man gang-equivalents) erect the wall lifts, moving to the next ready block while a floor is fitted; 1 joinery crew of 3 fits every intermediate floor and roof (Floors 1 day per plot, roofs 1 day per plot - one house; the 'floors' here are the GF ground-bearing slab (by others), the 1F floor (+ GF flat roofs) and the 2F metal-web joist floor). Programme is resource-levelled day by day (white = block waiting for a crew).

• Total ICF site programme: 5 working weeks (ICF erection, floors and roofs). Section A Preliminaries are quantified against this 5-week programme.

• EXTERNAL RENDER / FINISH IS EXCLUDED from this BOQ and this programme. Where a render system is later specified, allow a separate workstream — per BBA guidance, render cannot begin until the concrete core has cured for a minimum of 28 days after the final pour.

• Concrete pump booked on the pour days for each group (see Section C).

• Lead time for BuildEase Pre-Cut Service: 5–6 weeks from order placement; procurement runs in parallel with mobilisation.

• Programme estimates are provided in good faith and must be verified by the project / site management team.

• ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. Building height: the 2F (rooms in the roof) FFL is 5,800 above the GF FFL, ~5.95 m above the lowest adjoining ground (ADB Diagram D6, ground ASSUMED ~150 below GF FFL - to be confirmed on a measured survey); the main gable parapet apex is ~10.22 m above GF FFL (~10.4 m above ground) - BELOW 11 m on either measure, so the 11-18 m fire band does not apply. One detached dwelling, 3 storeys (GF / 1F / 2F in the roof) - within the LABC Warranty 3-storey limit for ICF (warranty provider to confirm); Consequence Class 1 house (Approved Document A).

• Floors 1 day per plot and roofs 1 day per plot - one house, so the GF slab slot, the 1F floor, the 2F floor and the roof are each shown at 1 day. The GF slot is the ground-bearing slab inside the FB walls (hardcore / DPM / 135 PIR / 200 RC / 65 screed, BY OTHERS - groundworker); the 1F and 2F floors are PS10-type metal-web joists top-hung on timber ledgers on the ICF and on timber packers in the indicative steels (joinery crew). The three GF warm flat roofs (GF wrap (den / WC + utility) 11.25 m2 / porch 2.57 m2 / bay 1.16 m2) are framed by the joinery crew with the 1F floor. Slab concrete, rebar and slab pumping are NOT in this ICF BOQ (coordination quantities in the finishes package Bill 6).

• Build sequence (no client programme issued): FB foundation (2 courses on the strip footing by others, Nudura Brick Ledge as the top course of the external walls) -> pour -> GF slab -> L1 GF walls (7 courses; the single-storey wrap / porch / bay parapets stop at 3,200) -> pour -> 1F floor (steels SB1-SB3 by others first) -> L2 1F walls (6 courses; the oriel from 4,343 on its corbel / steel; wing B eaves cut at 5,029) -> pour -> 2F floor (SB4 first) -> L3 2F walls (main gables raked to the parapet, eaves walls 6,858, wing B south gable, oriel cheeks + dormer gable) -> pour -> roof (cut roofs C24 @ 400, 50 deg). The stone / ashlar outer leaf on the Brick Ledge follows the ICF (stone contractor - not in this ICF programme).

• ICF pours sized at 60 m3 per pump per day from each lift's own concrete volume.

• PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3, floors and roofs 1 day per plot - one house, pours at 60 m3 / pump-day): 21 working days = 5 weeks. Sequence: ICF FB d0-0.22; pour d1-2; cure d2-4; GF ground-bearing slab d4-5; ICF L1 d5-6.16; pour d9-10; 1F metal-web joist floor d10-11; ICF L2 d11-11.94; pour d14-15; 2F metal-web joist floor d15-16; ICF L3 d16-16.62; pour d19-20; roof d20-21. ICF concrete 47.53 m3 (geometric, 309 ordered forms: FB 3.46 / L1 19.15 / L2 14.67 / L3 10.25) in 4 pump days. ALIGNMENT: the proposal prices 2 stillages x 8 weeks hire (GBP 1,280.00); on this programme the alignment is needed from the first ICF lift (FB, day 0) to the last pour (L3, day 20) = 4 weeks on hire - 4 weeks LESS than priced (GBP 640.00 of hire not needed on this programme). SENSITIVITY (BOQ Builder default: FB + L1 erected together and poured as one lift, the GF slab poured inside the walls off the ICF critical path): 16 working days = 4 weeks, 3 pump days, alignment on hire 3 weeks (-5 vs the 8 priced). The quotation has NOT been changed - confirm the hire period with the client / site team.

• Site access: corner plot at Clifton Park Road / Percival Road, Clifton (Bristol) - articulated delivery access, unloading and any parking suspension by the contractor for the 2 deliveries (18 pallets + 2 alignment stillages); a transfer to smaller vehicles is not included.

SUMMARY OF TENDER PRICING

Section totals are carried forward from each Bill section. Pre-priced columns show values from the associated Tremco CPG quotation; contractor-priced columns populate automatically when rates are entered in the section sheets. This BOQ excludes external render.

Section	Description	Pre-priced (£)	Contractor-priced (£)	Section Total (£)	
A	Preliminaries		£0.00	**£0.00**	
B	ICF Kit Supply	£22,628.39		**£22,628.39**	
C	Concrete Supply, Pump & Placement		£0.00	**£0.00**	
D	Labour — ICF, Floors & Roofs		£0.00	**£0.00**	
	NET TOTAL (excluding VAT)	**£22,628.39**	**£0.00**	**£22,628.39**	
	VAT @ 20%			£4,525.68	
	GRAND TOTAL (inclusive of VAT)			**£27,154.07**	

SIGNATURES

Priced by					
Tendered by					
Approved by					

A · PRELIMINARIES

Items priced per working week against the site programme total of 5 weeks (see Programme sheet). Quantities are pre-populated; the contractor inserts the weekly rate.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
A.1	Site set-up, fencing, signage, induction & welfare establishment	item	1		£0.00
A.2	Welfare facilities — canteen, drying, toilets (hire)	wk	5		£0.00
A.3	Contract management & site supervision	wk	5		£0.00
A.4	Health & Safety, RAMS, CDM consultancy	wk	5		£0.00
A.5	Public liability and contract works insurance	item	1		£0.00
A.6	Scaffolding — independent access for ICF erection	wk	5		£0.00
A.7	Plant hire — telehandler / forklift for offload & ICF moves	wk	5		£0.00
A.8	Plant hire — small tools, generators, power & lighting	wk	5		£0.00
A.9	Hoarding / site enclosure / security	wk	5		£0.00
A.10	Temporary services — water, power, lighting (hire)	wk	5		£0.00
A.11	Site clean, waste management & skip rotation	wk	5		£0.00
A.12	Setting out and surveying — engineer's level checks	wk	5		£0.00
A.13	Site take-down, hand-over & demobilisation	item	1		£0.00
A.14	Pre-completion sound test (Approved Document E)	test			£0.00
A.15	Air-tightness test (Approved Document L)	test			£0.00
A.16	Day works allowance	sum			£0.00
	A — PRELIMINARIES SUBTOTAL				**£0.00**

B · ICF KIT SUPPLY

ICF material supply values are pre-priced from the associated Tremco CPG quotation. Pre-cut service fees are taken from each BuildEase take-off.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
B.1 — ICF Block, Forms & Accessories					
B.1	ICF Materials — Clifton Park Road (1 plot(s), 309 forms)	group	1	£18,365.72	£18,365.72
B.2 — BuildEase Pre-Cut Service Fee					
B.2	Pre-Cut Service — Clifton Park Road	group	1	£1,857.91	£1,857.91
B.3 — Haulage					
B.3	Haulage to site — 2 loads: 2 x artic @ 180.0 mi (proposal delivery schedule: FB + L1, then L2 + L3)	item	1	£1,124.76	£1,124.76
B.4 — Alignment System					
B.4	Alignment System Rental — Clifton Park Road (31 systems)	group	1	£1,280.00	£1,280.00
	B — ICF KIT SUPPLY SUBTOTAL				**£22,628.39**

C · CONCRETE SUPPLY, PUMP & PLACEMENT

Volumes are geometric void calculations (block length × course height × core thickness). Allow ~3% for plastic web displacement and ~5% wastage when ordering. Rates to be inserted by the contractor.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
C.1 — Ready-Mix Concrete Supply (C28/35 typical to BS 8500)					
C.1	Ready-mix concrete — Clifton Park Road (1 plot(s), geometric void)	m³	47.53		£0.00
C.2 — Concrete Pump Hire					
C.2	Boom pump hire — Clifton Park Road	day	4		£0.00
C.2	Pump mobilisation / demobilisation	item	1		£0.00
C.3 — Concrete Vibration & Placement Plant					
C.3	Internal poker vibrator hire — site duration	wk	5		£0.00
C.3	Concrete banksman / poker operator	day			£0.00
	C — CONCRETE SUBTOTAL				**£0.00**

D · LABOUR — ICF INSTALL, FLOORS & ROOFS

ICF install days scaled proportionately against the Maycroft reference (52.65 forms per gang-day). Rates below are per 4-man gang per day. Floor and roof allowances are taken per group from the project configuration.

Ref	Description	Unit	Qty	Rate (£)	Total (£)
D.1 — ICF Install Gang					
D.1	ICF install — Clifton Park Road (309 forms ÷ 52.65 forms/day = 5.9 gang-days)	gang-day	5.90		£0.00
D.1	Snag, pour & cure attendance (30% allowance, project total)	gang-day	1.80		£0.00
D.2 — Floor Structure Labour (1F + 2F metal-web joists top-hung on ICF ledgers / steel packers, + 3 GF flat roofs; the GF slab slot is by other					
D.2	Floor structure — Clifton Park Road (3 floors × 1 gang-days)	gang-day	3		£0.00
D.3 — Roof Structure Labour (cut roofs C24 @ 400, 50 deg: main roof between the ICF parapet gables, wing B + oriel cross gables)					
D.3	Roof structure — Clifton Park Road	gang-day	1		£0.00
	D — LABOUR SUBTOTAL				**£0.00**

F · REFERENCE DATA (informative only)

Per-group quantities calculated from the BuildEase take-off models. Values feed into Sections C and D. Render is excluded from this BOQ.

Group	Plots	Forms	Concrete (m³)	ICF install days	Floor + Roof days	Pre-cut (£)
Clifton Park Road	1	309	47.53	5.90	4	£1,857.91
SITE	**1**	**309**	**47.53**	**5.90**	**4**	**£1,857.91**

PER-LIFT FORM BREAKDOWN

Group	Lift	4" Std	6" XR35 str	6" XR35 cnr	10" Std	Lift total
Clifton Park Road	FB	0	15	8	0	23
Clifton Park Road	L1	0	94	28	0	122
Clifton Park Road	L2	0	61	38	0	99
Clifton Park Road	L3	0	51	14	0	65

GEOMETRIC CONSTANTS & CALCULATION BASIS

Block length	2.438 m	*96 inches*
Course height	0.4574 m	*18 inches*
4" Std straight volume	0.1133 m³	*Volume = length × course × core*
6" XR35 straight volume	0.1699 m³	*Volume = length × course × core*
10" Std straight volume	0.2832 m³	*Volume = length × course × core*
4" Std corner volume	0.0511 m³	*L-void; long 31.625" / short 15.625"*
6" XR35 corner volume	0.1133 m³	*L-void; long 43" / short 27"*
Maycroft install rate	52.65 forms/day	*Reference: 1053 forms ÷ 20 days*

Bill of Quantities Package - Finishes & Ancillary Trades

ES26-065 | Clifton College Garage Site, Clifton Park Road | Cuckfield Real Estate Ltd

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Project	Clifton College Garage Site, Clifton Park Road
Site	Clifton College Garage Site, Clifton Park Road (corner of Percival Road), Clifton, Bristol
Client	Cuckfield Real Estate Ltd
Architect	O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3)
Quotation ref	ES26-065
Document	Bill of Quantities Package - Finishes & Ancillary Trades
Date	02/11/2026
Scope	One detached 3-storey house (GF, 1F, 2F rooms in the roof): 6in XR35 ICF external and internal load-bearing walls on an FB foundation with the Brick Ledge course, parapet gables, the single-storey GF wrap / porch / bay, wing B and the oriel; GF slab, metal-web joist floors, steels and cut roofs by others; coursed rubble + ashlar stone outer leaf, wing B render, clay double Roman tiles, timber windows
Building height	**ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. Building height: the 2F (rooms in the roof) FFL is 5,800 above the GF FFL, ~5.95 m above the lowest adjoining ground (ADB Diagram D6, ground ASSUMED ~150 below GF FFL - to be confirmed on a measured survey); the main gable parapet apex is ~10.22 m above GF FFL (~10.4 m above ground) - BELOW 11 m on either measure, so the 11-18 m fire band does not apply. One detached dwelling, 3 storeys (GF / 1F / 2F in the roof) - within the LABC Warranty 3-storey limit for ICF (warranty provider to confirm); Consequence Class 1 house (Approved Document A).**
Engineer / specialists	**ENGINEER / SPECIALISTS TO DESIGN: STRUCTURAL ENGINEER: the strip footing (sized for the Brick Ledge + stone outer leaf); masonry support / ties / lintels of the stone leaf above the ledge; the indicative steels SB1-SB4 and their bearings in the ICF core (pockets formed at the pour of the lift below); the oriel corbel / support; the 1F / 2F metal-web joist floors and ledgers (joist supplier); the cut roofs (rafters, collars, purlins, restraint to the parapet gables and the eaves walls). NOT FOR CONSTRUCTION.**
Prepared by	BuildEase (Tremco CPG UK) - BuildEase Design Suite quotation model
Status	**FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - rates blank; NOT part of the Nudura ICF price; NOT FOR CONSTRUCTION**

PACKAGE OVERVIEW - pricing by others (all amounts formula-linked to each bill's Package Summary)

Bill	Package	Code / NRM2	Supply £	Install £	Total £
Bill 1	External Walls - Stone Outer Leaf on the Brick Ledge (coursed rubble + ashlar), Render to Wing B	EXT NRM2 14 / 15	£0.00	£0.00	£0.00
Bill 2	Internal Linings - Walls, Ceilings (rooms in the roof on the slope), Tape, Beads & Skim	DRY NRM2 28	£0.00	£0.00	£0.00
Bill 3	Internal Doors & Ironmongery	JOI NRM2 24	£0.00	£0.00	£0.00
Bill 4	Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades	JOI NRM2 22	£0.00	£0.00	£0.00
Bill 5	Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings	JOI NRM2 16	£0.00	£0.00	£0.00
Bill 6	Substructure, GF Slab, Metal-Web Joist Floors, Steels & Oriel Corbel (coordination)	GRW / FLR / STR NRM2 5 / 11 / 14 / 16	£0.00	£0.00	£0.00
Bill 7	Roofs - Cut Roof Structure, Clay Double Roman Tiles, Rooflights, PV, Rainwater, Insulation & GF Flat Roofs	RFS / RFC NRM2 16 / 18	£0.00	£0.00	£0.00
Bill 8	Opening Schedule - Windows & External Doors (one line per opening, incl. accessories), Guarding	WIN NRM2 25	£0.00	£0.00	£0.00
	GRAND TOTAL - finishes / ancillary trades, net (excl. VAT)		**£0.00**	**£0.00**	**£0.00**

Optional additions (enter %; blank = 0)		**%**	**Amount £**
Preliminaries	on the finishes net grand total		£0.00
Overheads & profit	on net total + preliminaries		£0.00
Contingency	on net total + preliminaries + OH&P		£0.00
	GRAND TOTAL finishes incl. preliminaries, OH&P and contingency (excl. VAT)		**£0.00**

ICF PACKAGE HOOK - BuildEase BOQ Builder (ICF kit, concrete, labour, preliminaries, programme)	
Nudura ICF package (BuildEase BOQ Builder sheets of this workbook: Summary NET TOTAL)	**£22,628.39**
COMBINED TOTAL - finishes package (incl. additions) + ICF package, excl. VAT	**£22,628.39**

Pale-yellow cells are the only inputs (rates on each bill sheet, percentages and the ICF hook here). Everything else is a locked formula (protection has no password). Schedules A to D are reference only and are not priced. Named cells: FINISHES_NET_TOTAL, FINISHES_GRAND_TOTAL, ICF_PACKAGE_TOTAL, COMBINED_TOTAL.

IMPORTANT - This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

KEY QUANTITIES (site totals: one house, levels FB / L1 / L2 / L3, net; linked to the bills)		
Coursed rubble stone outer leaf	**106.59**	m2
Ashlar limestone outer leaf	**54.82**	m2
Render to wing B	**59.43**	m2
Wall linings (ICF faces, internal ICF walls, partitions, reveals)	**437.81**	m2
Ceilings (GF / 1F / 2F on the slope)	**176.84**	m2
Skim coat	**614.65**	m2
Internal doorsets	**12.00**	nr
Skirting	**198.20**	m
Timber stud partitions (gross area)	**125.67**	m2
Partition door openings formed	**12.00**	nr
Metal-web joist floors 1F / 2F	**98.56**	m2
Clay double Roman tiles on the slope	**104.18**	m2
GF warm flat roofs	**14.98**	m2
Windows	**16.00**	nr
External doors / glazed screen	**3.00**	nr

Document control

Issue	Description	Date	By / Status
-	Quotation issue: finishes / ancillary-trades BOQ package for the Nudura ICF quotation (per level FB / L1 / L2 / L3 for one detached house), merged with the BuildEase BOQ Builder ICF bill + programme. Live pricing workbook: rates blank for pricing by others; ICF_PACKAGE_TOTAL linked to the BOQ Builder NET TOTAL	02/11/2026	BuildEase - T. Smith / For information / pricing by others - NOT FOR CONSTRUCTION

Contents

Finishes Cover (this sheet) - overview
General Notes
Summary of Bills (section breakdown)
Finishes Bill 1 External Walls
Finishes Bill 2 Internal Lining
Finishes Bill 3 Doors
Finishes Bill 4 Joinery
Finishes Bill 5 Partitions
Finishes Bill 6 Floors
Finishes Bill 7 Roofs
Finishes Bill 8 Openings
Schedule A Areas (not priced)
Schedule B Openings (not priced)
Schedule C Per Level (not priced)
Schedule D Partitions (not priced)

General Notes, Measurement Basis, Assumptions & Exclusions

ES26-065 | Clifton College Garage Site, Clifton Park Road | Cuckfield Real Estate Ltd

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

1 Purpose, status, England and building height

ENGLAND: the design must satisfy the Building Regulations 2010 (Approved Documents A-S) - building control by LABC / an approved inspector. Building height: the 2F (rooms in the roof) FFL is 5,800 above the GF FFL, ~5.95 m above the lowest adjoining ground (ADB Diagram D6, ground ASSUMED ~150 below GF FFL - to be confirmed on a measured survey); the main gable parapet apex is ~10.22 m above GF FFL (~10.4 m above ground) - BELOW 11 m on either measure, so the 11-18 m fire band does not apply. One detached dwelling, 3 storeys (GF / 1F / 2F in the roof) - within the LABC Warranty 3-storey limit for ICF (warranty provider to confirm); Consequence Class 1 house (Approved Document A).

1.1

ENGINEER / SPECIALISTS TO DESIGN (floors, steels, roof timbers, partitions and glazing are in the model for coordination only): STRUCTURAL ENGINEER: the strip footing (sized for the Brick Ledge + stone outer leaf); masonry support / ties / lintels of the stone leaf above the ledge; the indicative steels SB1-SB4 and their bearings in the ICF core (pockets formed at the pour of the lift below); the oriel corbel / support; the 1F / 2F metal-web joist floors and ledgers (joist supplier); the cut roofs (rafters, collars, purlins, restraint to the parapet gables and the eaves walls).

1.2

This package presents the finishes and ancillary-trade quantities measured by BuildEase alongside the Nudura ICF quotation for Clifton College Garage Site, Clifton Park Road (ref ES26-065). It is set out as a Bill of Quantities so that the client, their quantity surveyor and trade contractors can price and coordinate the works.

1.3

Status: FOR INFORMATION, COORDINATION AND PRICING BY OTHERS - NOT FOR CONSTRUCTION. Supply and install rates are left blank deliberately - BuildEase / Tremco CPG are not pricing these trades. The Excel workbook is a live pricing document: enter rates and every amount, subtotal and total updates by formula.

1.4

The ICF kit, concrete core, pumping, ICF / floor / roof labour and the build programme are in the BuildEase BOQ Builder sheets of this workbook (Cover / Programme / Summary / A-F). The finishes cover carries a named hook (ICF_PACKAGE_TOTAL) linked to that NET TOTAL.

1.5

PROGRAMME (BOQ Builder sheet 'Programme', 1 ICF crew of 8 + 1 joinery crew of 3, floors and roofs 1 day per plot - one house, pours at 60 m3 / pump-day): 21 working days = 5 weeks. Sequence: ICF FB d0-0.22; pour d1-2; cure d2-4; GF ground-bearing slab d4-5; ICF L1 d5-6.16; pour d9-10; 1F metal-web joist floor d10-11; ICF L2 d11-11.94; pour d14-15; 2F metal-web joist floor d15-16; ICF L3 d16-16.62; pour d19-20; roof d20-21. ICF concrete 47.53 m3 (geometric, 309 ordered forms: FB 3.46 / L1 19.15 / L2 14.67 / L3 10.25) in 4 pump days. ALIGNMENT: the proposal prices 2 stillages x 8 weeks hire (GBP 1,280.00); on this programme the alignment is needed from the first ICF lift (FB, day 0) to the last pour (L3, day 20) = 4 weeks on hire - 4 weeks LESS than priced (GBP 640.00 of hire not needed on this programme). SENSITIVITY (BOQ Builder default: FB + L1 erected together and poured as one lift, the GF slab poured inside the walls off the ICF critical path): 16 working days = 4 weeks, 3 pump days, alignment on hire 3 weeks (-5 vs the 8 priced). The quotation has NOT been changed - confirm the hire period with the client / site team.

1.6

This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price.

1.7

Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

1.8

2 Basis of measurement

Measured generally in accordance with the principles of NRM2 (RICS New Rules of Measurement): work measured net as fixed in position, grouped by work section, units m / m2 / nr / item. NRM2 is referenced for structure only; descriptions are BuildEase's own.

2.1

Quantities are NET. No allowance for waste, laps, cutting or breakage is included unless stated; an "Order guide" with a stated waste % is guidance only.

2.2

Quantity columns: one column PER MODEL LEVEL - FB foundation, L1 GF (incl. the GF flat roofs and the 1F floor that bears on it), L2 1F (incl. the oriel and the 2F floor), L3 2F rooms in the roof + gables + ALL pitched-roof items. One house: the Site total is the sum of the columns (multiplier 1) and is a live formula.

2.3

Sources: O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); the BuildEase quotation model through its spec (04_Logs/specs/CL_spec.json, CL_flat.json, CL_partitions.json), build reports (04_Logs/build/CL: clw_fit, clf_* floors / steels / slab / stairs / oriel, roof_* / struct_*, flat_roofs, CLP_* TLSTF partitions) and the Report Tool component export (04_Logs/takeoff/CL_components.json: inner / outer EPS face areas of the 481 modelled forms, openings net). External finish areas from the ICF outer-face lines x the level heights / cut planes less the openings (Schedule A); finish split from PA113 / PA114.

2.4

3 Assumptions

Walls: external and internal load-bearing walls 6in XR35 (355.6 overall) on the drawn INNER face; drawn ~450 walls = ICF + stone / ashlar outer leaf on the Nudura Brick Ledge (top FB course). Frames tight to the back of the outer EPS (101.8): internal reveal 211.

3.1

Levels: FB -914.4 to 0 (2 courses on a strip footing by others); FFLs GF 0 / 1F 3,100 / 2F 5,800; GF single-storey parapets to 3,200; main eaves walls 6,858; parapet gables raked from 7,200 to ~10,216; wing B eaves 5,029, south gable to ~9,258; oriel from 4,343 to 7,315 + dormer gable.

3.2

External finishes per the elevations legend: coursed random rubble (main walls / gables), ashlar oolitic limestone (quoins, surrounds, GF wrap, bay, porch, GF rear, oriel), light render (wing B), dark red clay double Roman tiles, timber windows / doors, PPC glazed screen, painted cast RWG. Ground ~150 below GF FFL all round (not surveyed).

3.3

Floors: GF ground-bearing slab (clf_slab); 1F / 2F PS10 metal-web joists + 22 deck on ICF ledgers / steels (clf_floor_*), joist supplier design. Ceilings under them; the 2F rooms in the roof lined on the rafter slope to a collar ceiling ~7,950 (ASSUMED).

3.4

Internal doors: 12 doorsets / 13 leaves - TLSTF partition doors (GF / 1F) + 3 on the 2F plan; leaves = the largest standard 1,981 leaf that fits the opening less 68, pairs at 1,150 and over. Partitions: TLSTF 38 x 89 C16 - GF 6 walls 18.6 m / 1F 5 walls 18.3 m / 2F 7 walls 16.8 m = 53.6 m, 12 door openings (2F assumed - not modelled).

3.5

Roofs: 50 deg cut roofs (main between the parapet gables, wing B cross gable, oriel dormer), member counts from struct_*; slope area = plan x 1.556; valleys at equal pitch = run x 1.849; 3 rooflights and the PV array as drawn on the roof plan (not modelled).

3.6

4 Exclusions (not measured in this package)

Nudura ICF formwork and accessories incl. the Brick Ledge forms (in the Nudura price). ICF wall concrete, pumping, ICF / floor / roof labour and preliminaries are in the BOQ Builder sheets.

4.1

Supply of windows and doors is listed for pricing by the window / door suppliers (Bill 8) - not by BuildEase. External works, drainage, landscaping, boundary walls / gates, the ASHP and its base, the gardens.

4.2

Floor finishes, decorations, kitchens, sanitaryware, M&E services (heating, ventilation, electrics, PV system) and builder's work.

4.3

4.4 Fire-stopping and fire-rated service penetrations, sealants and mastics, except where expressly described.

5 Open items / to be confirmed

STRUCTURAL ENGINEER: the strip footing (sized for the Brick Ledge + stone outer leaf); masonry support / ties / lintels of the stone leaf above the ledge; the indicative steels SB1-SB4 and their bearings in the ICF core (pockets formed at the pour of the lift below); the oriel corbel / support; the 1F / 2F metal-web joist floors and ledgers (joist supplier); the cut roofs (rafters, collars, purlins, restraint to the parapet gables and the eaves walls).

5.1

ARCHITECT: the retained boundary stone wall on the Percival Road side (survey, the ICF stands inside it); roof covering - the elevations legend shows dark red clay double Roman tiles (measured as such); timber windows / doors (legend 5) and the stone mullion to L2-W01; the bay balustrade and access onto the bay roof; the 2F partition layout and the collar / ceiling line of the rooms in the roof; stair widths (not drawn).

5.2

BUILDING CONTROL (England, Approved Documents): ADB vol 1 - floor more than 4.5 m above ground (2F FFL 5.8 m): protected stairway / alternative; Part K - the 1F / 2F window sills 610-740 above floor need guarding; Part E internal walls / floors; Parts L / F / O; Part Q (PAS 24).

5.3

STONE SUPPLIER / MASON: the coursed rubble and ashlar outer leaf on the Brick Ledge (ties, movement joints, copings, kneelers, balustrade, cills, surrounds, quoins) - profiles and fixings; wing B render system or rendered masonry leaf (1C).

5.4

5.5 M&E: the PV array on the main east slope, rooflight blinds, ventilation strategy (ADF) and overheating (ADO).

Assumed (not drawn / not modelled): ground ~150 below GF FFL all round; Brick Ledge shelf ~457 below GF FFL; collar ceiling ~8,200 with the rafter soffit ~400 below the covering line; the 2F partitions (from the 2F plan) and 2F pattresses; stair widths 900; landing balustrades; downpipe positions; warm pitched roof over the 2F rooms with a cold loft over the collars; render direct on the ICF EPS to wing B.

5.6

6 What IS in the Nudura price (Quotation ES26-065, NET GBP 22,628.39)

Nudura ICF kit as modelled in the BuildEase Design Suite: 481 forms modelled (FB 55 / L1 189 / L2 143 / L3 94) / 329 to order after the cut optimiser (20 Standard Brick Ledge Form 6 inch, 88 XR35 90 Corner Form 6 inch, 221 XR35 Straight Form 6 inch), 6in XR35 walls with the Brick Ledge course, materials GBP 18,365.72.

6.1

6.2 Accessories: VJC clips, end caps, Form-Lock, lintel closures, T-straps, spray foam.

BuildEase Pre-Cut Service GBP 1,857.91; alignment system 2 stillages x 8 weeks hire GBP 1,280.00; haulage 2 loads: 2 x artic @ 180.0 mi GBP 1,124.76 (2 deliveries: FB + L1, then L2 + L3; 18 pallets).

6.3

6.4 Nothing in Bills 1 to 8 of this finishes package is included in the Nudura price.

7 Pricing instructions to tenderers

Each bill item has a SUPPLY rate and an INSTALL rate. Insert rates only in the pale-yellow cells of the Excel workbook: Supply = Site total qty x Supply rate; Install = Site total qty x Install rate; Line total = Supply + Install. Items measured as "item" are lump sums: the rate entered is the amount.

7.1

Each bill ends with a Package Summary (section subtotals for Supply / Install / Total and the package total). The Cover carries the full overview: one row per bill, grand totals, optional Preliminaries, Overheads & profit and Contingency percentages (pale-yellow cells; blank = 0) and the ICF package hook.

7.2

All other cells are locked by sheet protection (no password - Review > Unprotect Sheet if a change is genuinely needed) so formulas cannot be overwritten by accident.

7.3

Re-measure and verify all quantities before pricing or ordering. State any qualification against the item in the Notes column.

7.4

The Order guide figures and Schedules A to D are not measured bill items and must not be priced as such. All amounts exclude VAT.

7.5

Summary of Bills - section breakdown

ES26-065 | Clifton College Garage Site, Clifton Park Road | Cuckfield Real Estate Ltd - amounts by others, excl. VAT

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Bill	Section	Description	Supply £	Install £	Total £
1	1A	Natural stone outer leaf on the Nudura Brick Ledge (NRM2 14 - package EXT; stone supplier / mason, SPEC TBC)	£0.00	£0.00	£0.00
1	1B	Ashlar dressings, copings and stonework details (NRM2 14 - package EXT; stone supplier, profiles by the architect)	£0.00	£0.00	£0.00
1	1C	Render to wing B (NRM2 15 - package EXT; render system manufacturer)	£0.00	£0.00	£0.00
1	1D	DPCs, trays, weeps, joints and coordination (NRM2 14 - package EXT)	£0.00	£0.00	£0.00
Bill 1 - External Walls - Stone Outer Leaf on the Brick Ledge (coursed rubble + ashlar			**£0.00**	**£0.00**	**£0.00**
2	2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
2	2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	£0.00
Bill 2 - Internal Linings - Walls, Ceilings (rooms in the roof on the slope), Tape, Bead			**£0.00**	**£0.00**	**£0.00**
3	3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
3	3B	Ironmongery (NRM2 24 / package JOI)	£0.00	£0.00	£0.00
Bill 3 - Internal Doors & Ironmongery (package JOI)			**£0.00**	**£0.00**	**£0.00**
4	4A	Skirtings (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4B	Architraves (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4C	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	£0.00
4	4D	Stairs, balustrades and sundry joinery (NRM2 22 / package JOI) - INDICATIVE, stairs not modelled	£0.00	£0.00	£0.00
Bill 4 - Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades (package			**£0.00**	**£0.00**	**£0.00**
5	5A	Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5B	Partition timber - supply (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5C	Forming door openings in partitions (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
5	5D	Head restraint, acoustic, pattresses and fixings (NRM2 16 / package JOI)	£0.00	£0.00	£0.00
Bill 5 - Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings			**£0.00**	**£0.00**	**£0.00**
6	6A	Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	£0.00
6	6B	GF ground-bearing slab (NRM2 11 - package GRW; engineer)	£0.00	£0.00	£0.00
6	6C	1F floor (FFL 3,100) - metal-web joists + 22 deck (NRM2 16 - package FLR; joist supplier design)	£0.00	£0.00	£0.00
6	6D	2F floor (FFL 5,800) - metal-web joists + 22 deck (NRM2 16 - package FLR; joist supplier design)	£0.00	£0.00	£0.00
6	6E	Steels and the oriel corbel (NRM2 14 - package STR; ENGINEER - INDICATIVE, sections not designed)	£0.00	£0.00	£0.00
Bill 6 - Substructure, GF Slab, Metal-Web Joist Floors, Steels & Oriel Corbel (coordina			**£0.00**	**£0.00**	**£0.00**
7	7A	Roof structure - cut roofs C24 @ 400 (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	£0.00
7	7B	Roof coverings, eaves, rainwater and abutments (NRM2 18 / 33 - package RFC)	£0.00	£0.00	£0.00
7	7C	Roof insulation and VCL (NRM2 18 / 28 - package RFC)	£0.00	£0.00	£0.00
7	7D	GF warm flat roofs (NRM2 18 - package RFC)	£0.00	£0.00	£0.00
Bill 7 - Roofs - Cut Roof Structure, Clay Double Roman Tiles, Rooflights, PV, Rainwater			**£0.00**	**£0.00**	**£0.00**
8	8A	Opening schedule - windows and external doors, one line per opening incl. accessories (NRM2 25 - package WIN; window / door supplier)	£0.00	£0.00	£0.00
8	8B	Guarding, security and items not modelled (PROVISIONAL)	£0.00	£0.00	£0.00
Bill 8 - Opening Schedule - Windows & External Doors (one line per opening, incl. acc			**£0.00**	**£0.00**	**£0.00**
TOTAL - finishes / ancillary trades, net (agrees with the Cover overview)			**£0.00**	**£0.00**	**£0.00**

Schedules A to D are reference schedules and are not priced. Preliminaries, overheads & profit, contingency and the ICF package (BuildEase BOQ Builder) are applied on the Cover.

Bill 1 - External Walls - Stone Outer Leaf on the Brick Ledge (coursed rubble + ashlar), Render to Wing B

Coursed rubble and ashlar stone outer leaf on the Nudura Brick Ledge, ashlar dressings, copings, the bay balustrade, wing B render, DPCs and trays (by others, spec TBC). [NRM2 14 / 15 / package EXT]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
1A	**Natural stone outer leaf on the Nudura Brick Ledge (NRM2 14 - package EXT; stone supplier / mason, SPEC TBC)**												
	O'Leary Goss elevations PA113 C / PA114 C (materials legend): (1) coursed random rubble stone to the main house walls and gables, (2) ashlar oolitic limestone to the quoins, surrounds, the single-storey GF wrap, the bay, the porch, the GF rear and the oriel, (3) light render to wing B. The stone is an OUTER LEAF (~100) standing on the Nudura Brick Ledge course (top FB course, ledge ~457 below GF FFL) and tied back to the ICF webs. Areas = the ICF outer-face lines (spec chains) x the level heights / cut planes (eaves 6,858, raked parapet gables, wing B eaves 5,029 + raked south gable, oriel), less the spec openings; the exposed FB band from ground (~150 below GF FFL, ASSUMED) to FFL is in the FB column. Masonry support above the ledge (ties, lintels, movement joints) by the engineer / stone supplier.												
1A.1	Coursed random rubble natural stone outer leaf (~100 bed), lime mortar, tied to the ICF, main house walls and parapet gables, net of openings (quoins / surrounds measured over - 1B)	m2	0.70	15.01	54.60	36.28	**106.59**			£0.00	£0.00	**£0.00**	Order guide +10% = 117.2
1A.2	Ashlar oolitic limestone outer leaf (~100 sawn bed), lime mortar, tied to the ICF: GF wrap, bay, porch, GF rear, oriel, net of openings	m2	2.86	41.27	4.48	6.20	**54.82**			£0.00	£0.00	**£0.00**	Order guide +10% = 60.3
1A.3	Below-ground outer leaf from the Brick Ledge shelf (~-457) to ground (~-150): engineering brick / dense block, frost resistant, on the ledge, all external walls except the retained boundary wall	m2	9.92				**9.92**			£0.00	£0.00	**£0.00**	32.3 m x 0.307
1A.4	Stainless steel wall ties / ICF tie anchors to the stone leaf, 2.5 per m2 + extra at openings and movement joints (product per the stone supplier / ICF tie system)	nr	33.71	140.69	147.72	106.21	**428.32**			£0.00	£0.00	**£0.00**	Estimate - tie density by the engineer
1A.5	Ashlar quoins (alternate long / short) to the four main-house corners, 1F and the gable shoulders (GF corners are ashlar walling)	m			10.97	5.03	**16.00**			£0.00	£0.00	**£0.00**	INDICATIVE - elevations PA113 / PA114
1B	**Ashlar dressings, copings and stonework details (NRM2 14 - package EXT; stone supplier, profiles by the architect)**												
	Read off the elevations: ashlar surrounds to the openings in the rubble walls, stone cills to every window, a stone (or stainless) lintel / support over every opening in the stone leaf, copings to the raked main gable parapets and to the single-storey GF parapets, a stone balustrade over the bay, the oriel corbel. Numbers from the spec openings, lengths from the spec chains - INDICATIVE.												
1B.1	Ashlar surround (jambs + head, ~150 face, returned into the reveal) to the openings in the coursed rubble walls	m			16.71	9.26	**25.97**			£0.00	£0.00	**£0.00**	L2-W01, L2-W03, L2-W05, L2-W06, L3-W01, L3-W02
1B.2	Ashlar window cills, weathered + throated, stooled ends, 50 horns each end, bedded on a DPC tray	m		4.45	9.15	3.11	**16.71**			£0.00	£0.00	**£0.00**	L1 5 nr, L2 8 nr, L3 3 nr
1B.3	Lintel / masonry support over each opening in the stone leaf (stone lintel or stainless angle, 150 bearings) - engineer	m		10.84	8.11	2.94	**21.89**			£0.00	£0.00	**£0.00**	L1 7 nr, L2 5 nr, L3 2 nr
1B.4	Ashlar coping to the raked main-gable parapets (front + rear, 4 rakes, shoulder to apex), DPC under, cramped	m				15.75	**15.75**			£0.00	£0.00	**£0.00**	Order guide +10% = 17.3
1B.5	Gable kneelers (springers) and apex stones to the two parapet gables	nr				6.00	**6.00**			£0.00	£0.00	**£0.00**	2 kneelers + 1 apex per gable
1B.6	Ashlar parapet + coping to the single-storey GF wrap, porch and GF rear (parapet above the ICF top 3,200 to the drawn ~3.3-3.6 m), DPC under	m		8.28			**8.28**			£0.00	£0.00	**£0.00**	Outer edges outside the 1F footprint; excludes the bay (1B.7) and the retained boundary wall
1B.7	Stone balustrade over the bay (plinth, balusters, handrail, end piers) - PROVISIONAL (access / guarding by the architect)	m		5.66			**5.66**			£0.00	£0.00	**£0.00**	Bay outer faces
1B.8	Oriel: ashlar corbel / soffit under the oriel (over the corbel / steel by the engineer), carved profile to the architect	m2			1.67		**1.67**			£0.00	£0.00	**£0.00**	Oriel plan 837 x 1,990
1C	**Render to wing B (NRM2 15 - package EXT; render system manufacturer)**												
	Elevations: wing B (kitchen / utility below, bathroom / en-suite above) in a LIGHT RENDER - front 1F, rear GF + 1F and the full south gable. ASSUMED a thin-coat render system direct on the ICF EPS (mesh + basecoat + through-coloured finish); if a rendered masonry leaf on the Brick Ledge is wanted instead, re-measure (architect).												

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
1C.1	Render system on the ICF EPS: adhesive basecoat + alkali-resistant mesh + primer + through-coloured silicone finish (light), net of openings	m2	1.28	26.58	22.61	8.96	**59.43**			£0.00	£0.00	**£0.00**	Order guide +10% = 65.4
1C.2	Render reveal returns, head + jambs (102 girth)	m2		0.32	0.87	0.16	**1.36**			£0.00	£0.00	**£0.00**	Order guide +10% = 1.5
1C.3	Render beads: corner beads to the wing B external corners + stop / reveal beads at the openings	m		9.86	12.23	1.59	**23.69**			£0.00	£0.00	**£0.00**	Order guide +10% = 26.1
1C.4	Render base / starter bead with drip at the plinth line (render to stop above ground, plinth below)	m	8.53				**8.53**			£0.00	£0.00	**£0.00**	Order guide +10% = 9.4
1D DPCs, trays, weeps, joints and coordination (NRM2 14 - package EXT)													
1D.1	DPC / cavity tray at the base of the stone leaf on the Brick Ledge, with weep vents at 900 c/c	m	32.29				**32.29**			£0.00	£0.00	**£0.00**	Order guide +10% = 35.5
1D.2	Cavity tray with stop ends + weep vents over each opening in the stone leaf	nr		7.00	5.00	2.00	**14.00**			£0.00	£0.00	**£0.00**	One per opening in the stone leaf
1D.3	External perimeter seal between the stone / render reveal and the window / door frames (backer rod + low-modulus sealant)	m		42.74	28.90	10.85	**82.49**			£0.00	£0.00	**£0.00**	Order guide +10% = 90.7
1D.4	Movement joints in the stone leaf (vertical per the stone supplier / engineer, incl. at the junctions with wing B render)	item								£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance - stone supplier
1D.5	Retained boundary stone wall (GF wrap left, Percival Road side): the ICF stands inside it with NO new facing - survey, repair / repoint the existing wall, junction / weathering at its head and the ICF behind - PROVISIONAL	m2	1.03	23.07			**24.10**			£0.00	£0.00	**£0.00**	6.9 m long; condition / height by survey (RFI)

PACKAGE SUMMARY - Bill 1 External Walls - Stone Outer Leaf on the Brick Ledge (coursed rubble + ashlar), Render to Wing B (package EXT; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
1A	Natural stone outer leaf on the Nudura Brick Ledge (NRM2 14 - package EXT; stone supplier / mason, SPEC TBC)	£0.00	£0.00	**£0.00**
1B	Ashlar dressings, copings and stonework details (NRM2 14 - package EXT; stone supplier, profiles by the architect)	£0.00	£0.00	**£0.00**
1C	Render to wing B (NRM2 15 - package EXT; render system manufacturer)	£0.00	£0.00	**£0.00**
1D	DPCs, trays, weeps, joints and coordination (NRM2 14 - package EXT)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 1, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

BuildEase

Bill 2 - Internal Linings - Walls, Ceilings (rooms in the roof on the slope), Tape, Beads & Skim

Dry linings to the ICF inner faces (thermal barrier to the EPS), internal ICF walls, TLSTF partitions, reveals, ceilings under the joist floors / flat roofs and the 2F rooms in the roof. [NRM2 28 / package DRY]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
2A Wall linings (NRM2 28 / package DRY)													
	Measured on the modelled ICF inner EPS faces (Report Tool component export, openings net) by height zone: GF 0-2,825 (underside of the 1F metal-web joists), 1F 3,100-5,525, 2F 5,800 to the collar ceiling ~7,950 (ASSUMED); the joist zones are not lined. The oriel inner faces in full. The internal ICF load-bearing walls (GF hall / den and wing front) both faces. TLSTF partitions both faces, door gaps deducted. EPS faces must be covered by a thermal barrier (min. 12.5 mm board mechanically fixed to the ICF webs) whatever the finish - incl. the gable faces in the cold loft above the collar.												
2A.1	GF ICF external-wall inner faces: 12.5 mm wallboard on dabs + mechanical fixings to the ICF webs (MR board in the WC / utility / kitchen)	m2		77.90			**77.90**			£0.00	£0.00	**£0.00**	Order guide +10% = 85.7
2A.2	1F ICF external-wall inner faces (incl. wing B): 12.5 mm wallboard on dabs + mechanical fixings (MR in the bathroom / en-suite)	m2		3.51	60.66		**64.16**			£0.00	£0.00	**£0.00**	Order guide +10% = 70.6
2A.3	2F ICF inner faces: eaves knee walls + the gables to the collar ceiling: 12.5 mm wallboard on dabs + mechanical fixings (MR in the shower room)	m2			4.06	36.08	**40.14**			£0.00	£0.00	**£0.00**	Order guide +10% = 44.2
2A.4	Oriel ICF inner faces (1F + 2F): 12.5 mm wallboard on dabs + mechanical fixings	m2			4.00	4.53	**8.53**			£0.00	£0.00	**£0.00**	Order guide +10% = 9.4
2A.5	Internal ICF load-bearing walls (GF), both faces: 12.5 mm wallboard on dabs + mechanical fixings	m2		16.78			**16.78**			£0.00	£0.00	**£0.00**	Order guide +10% = 18.5; 2.97 m of wall
2A.6	Gable inner faces in the cold loft above the collar ceiling (~7,950): 12.5 mm board mechanically fixed - THERMAL BARRIER to the EPS only (no skim)	m2				9.17	**9.17**			£0.00	£0.00	**£0.00**	Order guide +10% = 10.1
2A.7	TLSTF partitions - both faces: 12.5 mm board on 38 x 89 studs (MR in the wet rooms; acoustic board / quilt per Part E E2)	m2		89.65	73.35	49.87	**212.87**			£0.00	£0.00	**£0.00**	Order guide +10% = 234.2; 2F partitions ASSUMED (Bill 5)
2A.8	Internal reveals to windows / doors in the ICF, jambs and heads, 211 deep: board / bonding + skim	m2		9.03	6.11	2.29	**17.43**			£0.00	£0.00	**£0.00**	Order guide +10% = 19.2
2B Ceilings (NRM2 28 / package DRY)													
	GF: under the 1F metal-web joist floor (50.19 m2) and the three GF flat roofs (14.98 m2), less the partition footprints. 1F: under the 2F floor (48.37 m2) + the wing B strips under the roof slopes (2.90 m2). 2F rooms in the roof: board on the rafter soffits ON THE SLOPE from the knee walls (~1,039 above 2F FFL) to a flat collar ceiling at ~7,950 (ASSUMED; collar ceiling ~2.48 m wide), plus the wing B room and the oriel on the slope.												
2B.1	GF ceilings: 12.5 mm board (15 mm where the fire strategy needs) to the metal-web joist bottom chords / flat-roof joists	m2		62.96			**62.96**			£0.00	£0.00	**£0.00**	Order guide +10% = 69.3
2B.2	1F ceilings: 12.5 mm board to the 2F joist bottom chords and the wing B ceiling joists / rafters	m2			49.10		**49.10**			£0.00	£0.00	**£0.00**	Order guide +10% = 54.0
2B.3	2F rooms in the roof: 12.5 mm board to the rafter soffits (slope) + the collar ceiling - over the insulation / VCL (Bill 7C)	m2				64.78	**64.78**			£0.00	£0.00	**£0.00**	Order guide +10% = 71.3
2C Jointing, beads and skim (NRM2 28 / package DRY)													
2C.1	Scrim tape, board joints (walls / 1.2 m; ceilings / 1.2 + 2.4 m)	m		242.76	184.84	158.29	**585.89**			£0.00	£0.00	**£0.00**	Order guide +10% = 644.5
2C.2	Scrim tape, internal angles wall to wall (4 per partition + 4 per ICF internal wall + the reflex ICF corners)	m		96.05	53.35	51.75	**201.15**			£0.00	£0.00	**£0.00**	Estimate - no room model; Order guide +10% = 221.3
2C.3	Scrim tape, wall to ceiling angles (ICF inner perimeter + partition heads both sides; 2F incl. the knee / collar lines)	m		73.66	68.14	94.27	**236.08**			£0.00	£0.00	**£0.00**	Estimate; Order guide +10% = 259.7
2C.4	Angle bead, window / door reveals	m		42.74	28.90	10.85	**82.49**			£0.00	£0.00	**£0.00**	Order guide +10% = 90.7
2C.5	Skim coat, 2-3 mm, to all net wall, reveal and ceiling board faces (not the loft thermal barrier)	m2		259.83	197.26	157.55	**614.65**			£0.00	£0.00	**£0.00**	Face layer only

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
2D Ordering guide (not a measured item)													
2D.1	*Plasterboard to purchase, all types, before waste*	*m2*		*259.83*	*197.26*	*166.73*	*623.82*					*not priced*	*Guide only (+10% waste)*

PACKAGE SUMMARY - Bill 2 Internal Linings - Walls, Ceilings (rooms in the roof on the slope), Tape, Beads & Skim (package DRY; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
2A	Wall linings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2B	Ceilings (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
2C	Jointing, beads and skim (NRM2 28 / package DRY)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 2, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 3 - Internal Doors & Ironmongery

Internal doorsets and ironmongery per level from the TLSTF partition doors and the 2F plan (12 doorsets, 13 leaves). [NRM2 24 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
3A	**Internal doorsets (NRM2 24 / package JOI)**												
	From the TLSTF door reports (GF / 1F, 9 openings) and the 2F plan (3 openings - 2F partitions ASSUMED, not modelled). Leaf = the largest standard 1,981 leaf that fits the opening less 68 (2 x 32 lining + clearances); openings of 1,150 and over get a PAIR. ENGLAND: ADB vol 1 - a house with a floor more than 4.5 m above ground (2F FFL 5.8 m) needs a protected stairway (FD20 doors onto the stair enclosure, or sprinklers / an alternative escape) - architect / building control.												
3A.1	Bifold cupboard doorset, PAIR of 533 x 1,981 folding leaves, 32 x 115 lining set, top track + pivots	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	GF-D03 (1200)
3A.2	Cupboard doorset, 533 x 1,981 leaf (cut to suit), 32 x 115 lining set, stops	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	1F-D03 (600)
3A.3	Internal doorset, 711 x 1,981 leaf, 32 x 115 lining set (119 partition), stops	nr		3.00	2.00	2.00	**7.00**			£0.00	£0.00	**£0.00**	GF-D01 (820), GF-D02 (800), GF-D04 (800), 1F-D01 (800), 1F-D05 (800), 2F-D01 (800), 2F-D03 (800)
3A.4	Internal doorset, 610 x 1,981 leaf, 32 x 115 lining set (119 partition), stops	nr			2.00	1.00	**3.00**			£0.00	£0.00	**£0.00**	1F-D02 (700), 1F-D04 (750), 2F-D02 (700)
3A.5	Upgrade the doors onto the stair enclosure (GF / 1F / 2F) to FD20 IF the fire strategy uses a protected stairway (ADB vol 1, floor > 4.5 m) - PROVISIONAL	item			1.00		**1.00**			£0.00	£0.00	**£0.00**	Fire strategy / building control
3B	**Ironmongery (NRM2 24 / package JOI)**												
3B.1	Butt hinges, 100 mm, pairs (1.5 pair per hinged leaf)	pr		4.50	7.50	4.50	**16.50**			£0.00	£0.00	**£0.00**	1.5 pr per leaf (bifolds on their track)
3B.2	Standard sets: tubular latch, lever pair on roses	set		3.00	2.00	2.00	**7.00**			£0.00	£0.00	**£0.00**	Doors to the rooms
3B.3	Bathroom / WC sets: privacy lock, thumb-turn with emergency release, lever pair	set		1.00	2.00	1.00	**4.00**			£0.00	£0.00	**£0.00**	GF-D02, 1F-D02, 1F-D04, 2F-D02
3B.4	Cupboard sets: magnetic / roller catch + knob or pull handle	set		1.00	1.00		**2.00**			£0.00	£0.00	**£0.00**	GF-D03, 1F-D03
3B.5	Door stops, floor or skirting mounted	nr		3.00	4.00	3.00	**10.00**			£0.00	£0.00	**£0.00**	One per room door leaf

The external doors (main entrance, service door, PPC sliding screen) are in the opening schedule (Bill 8).

PACKAGE SUMMARY - Bill 3 Internal Doors & Ironmongery (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
3A	Internal doorsets (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
3B	Ironmongery (NRM2 24 / package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 3, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 4 - Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades

Second-fix joinery: skirtings, architraves, window boards, the two staircases (indicative) and balustrades. [NRM2 22 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
4A	**Skirtings (NRM2 22 / package JOI)**												
	No room model: every lined wall face at floor level - the ICF inner perimeter less the external door openings, the internal ICF walls both faces, TLSTF partitions both faces less their door openings; 2F = the knee walls / gables of the main rooms + the wing B room. 18 x 144 MDF, profile by the client.												
4A.1	Skirting 18 x 144 MDF, primed, fixed to the linings	m		67.03	60.84	70.33	**198.20**			£0.00	£0.00	**£0.00**	Order guide +10% = 218.0
4B	**Architraves (NRM2 22 / package JOI)**												
	Per face = 2 legs x 2150 + (opening + 2 x 70). Internal doors both faces; external doors inside face only; windows have plastered reveals (no architrave).												
4B.1	Architrave 18 x 69 MDF, primed, mitred	m		64.07	51.70	31.24	**147.01**			£0.00	£0.00	**£0.00**	Order guide +10% = 161.7
4C	**Window boards (NRM2 22 / package JOI)**												
	Every window: board = opening + 2 x 50 horns, depth = internal reveal 211 + 25 nosing. The bay and the oriel windows to the bay / oriel plan.												
4C.1	Window board 25 MDF / hardwood, bullnosed, 236 deep, horns + returned ends	m		4.45	9.15	3.11	**16.71**			£0.00	£0.00	**£0.00**	Order guide +10% = 18.4; L1 5 nr, L2 8 nr, L3 3 nr
4D	**Stairs, balustrades and sundry joinery (NRM2 22 / package JOI) - INDICATIVE, stairs not modelled**												
	From the stair check (clf_stairs.json): GF-1F 15 risers of 206.7, going 220; 1F-2F 13 risers of 207.7, going 220 (ADK: rise <= 220, 2R + G 550-700, headroom 2.0 m - checked). Width NOT drawn - 900 ASSUMED. Balustrade lengths on the rake from the flights; landing balustrades provisional.												
4D.1	Softwood / MDF staircase GF-1F, 15 risers x 206.7, going 220, ~900 wide (ASSUMED), closed strings, newels, fixed to the ICF / partitions (shape to the architect's plan)	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	Architect / stair manufacturer
4D.2	Softwood / MDF staircase 1F-2F, 13 risers x 207.7, going 220, ~900 wide (ASSUMED), closed strings, newels, fixed to the ICF / partitions (shape to the architect's plan)	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	Architect / stair manufacturer
4D.3	Balustrade on the rake (handrail, base rail, spindles <100 gap, 900 high) - one side of each flight	m		4.23	3.63		**7.86**			£0.00	£0.00	**£0.00**	Order guide +10% = 8.6
4D.4	Wall handrail on brackets, the wall side of each flight (fixings into the ICF / partitions)	m		4.23	3.63		**7.86**			£0.00	£0.00	**£0.00**	Order guide +10% = 8.6
4D.5	Landing balustrade around the stairwell, 1F + 2F (1,000 high) - PROVISIONAL	m			3.00	2.50	**5.50**			£0.00	£0.00	**£0.00**	Allowance - stair well not modelled
4D.6	Insulated, draught-sealed loft hatch + ladder to the cold loft over the 2F collar ceiling	nr				1.00	**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL
4D.7	Boxing-in of services / soil pipes, airing cupboard shelving, ironing / store cupboard fittings	item								£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. Allowance

PACKAGE SUMMARY - Bill 4 Joinery - Skirtings, Architraves, Window Boards, Stairs & Balustrades (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
4A	Skirtings (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4B	Architraves (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4C	Window boards (NRM2 22 / package JOI)	£0.00	£0.00	**£0.00**
4D	Stairs, balustrades and sundry joinery (NRM2 22 / package JOI) - INDICATIVE, stairs not modelled	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 4, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 5 - Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings

Non-loadbearing 38 x 89 C16 timber stud partitions (GF 6 walls 18.6 m / 1F 5 walls 18.3 m / 2F 7 walls 16.8 m = 53.6 m, 12 door openings (2F assumed - not modelled)). Linings in Bill 2, doorsets in Bill 3. [NRM2 16 / package JOI]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		**1**	**1**	**1**	**1**	**4**						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
5A	**Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)**												
	C16 softwood stud partitions (GF 6 walls 18.6 m / 1F 5 walls 18.3 m / 2F 7 walls 16.8 m = 53.6 m, 12 door openings (2F assumed - not modelled)): GF / 1F as built in the TLSTF model - 38 x 89 studs at 600 c/c (400 at the wet-room wall: cl_int_89_600 6, cl_int_89_400 5), head and bottom rails, noggins; GF FFL to the 1F joist underside (2,825), 1F to the 2F joist underside (2,425). 2F partitions from the 2F plan, NOT modelled: heights follow the ASSUMED rafter soffit / collar ceiling (mean 1,725). Gross area, door openings NOT deducted (5C). The load-bearing walls are ICF (Nudura).												
5A.1	GF partitions (6 walls, 18.6 m x 2,825): 38 x 89 C16 studs, head + bottom rails, noggins	m2		52.43			**52.43**			£0.00	£0.00	**£0.00**	wall length x height
5A.2	1F partitions (5 walls, 18.3 m x 2,425): 38 x 89 C16 studs, head + bottom rails, noggins	m2			44.34		**44.34**			£0.00	£0.00	**£0.00**	wall length x height
5A.3	2F partitions (7 walls, 16.8 m x mean 1,725): 38 x 89 C16 studs, head + bottom rails, noggins - ASSUMED (not modelled; raked heads under the roof)	m2				28.90	**28.90**			£0.00	£0.00	**£0.00**	wall length x height
5B	**Partition timber - supply (NRM2 16 / package JOI)**												
	ESTIMATE in linear metres of 38 x 89 C16 kiln-dried sawn softwood: studs from the TLSTF verify reports (stud counts x stud length GF 2,787 / 1F 2,387; 2F at 600 c/c x the mean height), bottom rails (door gaps cut out) + head rails, one noggin row and 2 king studs + head per door. TLSTF members: GF 204, 1F 261. Supply only.												
5B.1	38 x 89 C16 kiln-dried sawn softwood: studs	m		117.05	128.90	62.66	**308.62**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.2	38 x 89 C16 kiln-dried sawn softwood: bottom + head rails	m		33.50	32.92	31.21	**97.62**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.3	38 x 89 C16 kiln-dried sawn softwood: noggins (one row)	m		18.56	18.29	16.75	**53.60**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.4	38 x 89 C16 kiln-dried sawn softwood: king studs and heads at door openings	m		21.22	25.65	12.65	**59.52**			£0.00	£0.00	**£0.00**	Estimate - see 5B note
5B.5	*38 x 89 C16 lengths to order (run +10%, 4.8 m lengths)*	*nr*		*44.00*	*48.00*	*29.00*	*121.00*					*not priced*	*Ordering guide only - not priced in addition*
5C	**Forming door openings in partitions (NRM2 16 / package JOI)**												
	From the TLSTF door reports + the 2F plan (12 openings). Per opening: 2 full-height king studs, head at ~2,100, cripples over, bottom rail cut out. Timber in 5B.												
5C.1	Form door opening 600 wide x ~2,100 high in the 89 partition	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.2	Form door opening 700 wide x ~2,100 high in the 89 partition	nr			1.00	1.00	**2.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.3	Form door opening 750 wide x ~2,100 high in the 89 partition	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.4	Form door opening 800 wide x ~2,100 high in the 89 partition	nr		2.00	2.00	2.00	**6.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.5	Form door opening 820 wide x ~2,100 high in the 89 partition	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5C.6	Form door opening 1,200 wide x ~2,100 high in the 89 partition	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	Doorsets in Bill 3
5D	**Head restraint, acoustic, pattresses and fixings (NRM2 16 / package JOI)**												
	Heads: galvanised slotted partition head clips to the metal-web joist bottom chords / noggins (5 mm deflection gap), from the TLSTF ceiling-noggin reports (GF 33 clips + 3 noggins; 1F 43 clips + 9 noggins). 2F heads fixed to the collars / rafters (noggins between). Pattresses: 18 WBP ply in the stud bays on the wet-room faces (TLSTF pattress reports).												
5D.1	Slotted partition head clip, galvanised, head rail to the joist bottom chord (product to confirm)	nr		33.00	43.00		**76.00**			£0.00	£0.00	**£0.00**	TLSTF ceiling-noggin reports
5D.2	47 x 97 C24 noggins between the joist bottom chords over partitions parallel to the joists (on Z clips)	nr		3.00	9.00		**12.00**			£0.00	£0.00	**£0.00**	TLSTF ceiling-noggin reports
5D.3	2F partition heads: noggins / fixings to the collars and rafters (raked heads) - ASSUMED	nr				7.00	**7.00**			£0.00	£0.00	**£0.00**	One per 2F wall
5D.4	Fix bottom rails to the screed / deck at max 600 c/c on a DPC strip	m		14.94	14.64	14.45	**44.03**			£0.00	£0.00	**£0.00**	Bottom rail length (door gaps excluded)

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
5D.5	Acoustic mineral wool quilt (min 10 kg/m3, 25 thick) in the partition voids - Part E E2 internal walls (Rw 40) round bedrooms / bathrooms	m2		52.43	44.34	28.90	**125.67**			£0.00	£0.00	**£0.00**	Allow all partitions - reduce to the room layout
5D.6	18 WBP ply pattress pieces in the stud bays for sanitaryware / wall-hung fittings (150-1,950 above floor)	nr		8.00	34.00	6.00	**48.00**			£0.00	£0.00	**£0.00**	TLSTF pattress reports; 2F shower room ASSUMED 6
5D.7	Nails, screws, framing fixings and sundries for the partition framing	item								£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount.

PACKAGE SUMMARY - Bill 5 Timber Stud Partitions (TLSTF) - Framing, Openings, Head Restraint & Fixings (package JOI; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
5A	Timber stud partitions, non-loadbearing - framing (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5B	Partition timber - supply (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5C	Forming door openings in partitions (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
5D	Head restraint, acoustic, pattresses and fixings (NRM2 16 / package JOI)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 5, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 6 - Substructure, GF Slab, Metal-Web Joist Floors, Steels & Oriel Corbel (coordination)

Strip footing, FB protection, GF ground-bearing slab, the 1F / 2F metal-web joist floors, indicative steels and the oriel corbel (by others - engineer / suppliers). [NRM2 5 / 11 / 14 / 16 / package GRW / FLR / STR]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
6A Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)													
	The ICF FB foundation (2 courses, -914 to 0) stands on a concrete strip footing BY OTHERS (size by the engineer - not in the model), under the external walls and the internal ICF load-bearing walls. The top FB course on the external walls is the Nudura Brick Ledge carrying the stone outer leaf (Bill 1). Ground ~150 below GF FFL ASSUMED (not surveyed); Clifton - check the radon map / site investigation (Bristol).												
6A.1	Concrete strip footing under the ICF FB walls (centre-line length; width / depth / reinforcement by the engineer, wide enough for the Brick Ledge + stone leaf)	m	40.83				**40.83**			£0.00	£0.00	**£0.00**	ICF centre line incl. the internal ICF walls
6A.2	Protection / DPM to the below-ground FB outer EPS faces (dimpled membrane or protection board) before backfill	m2	31.01				**31.01**			£0.00	£0.00	**£0.00**	Order guide +10% = 34.1
6A.3	Backfill / drainage aggregate against the FB walls and a perimeter land drain if the engineer requires - PROVISIONAL	m	39.18				**39.18**			£0.00	£0.00	**£0.00**	Building outline at the ICF outer faces
6A.4	Radon / ground-gas protection (membrane + sealed service entries) IF the site investigation requires	item								£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. PROVISIONAL
6B GF ground-bearing slab (NRM2 11 - package GRW; engineer)													
	GF slab inside the ICF inner faces (72.54 m2, clf_slab.json): 200 compacted hardcore, blinding + DPM, 200 RC ground-bearing slab, 135 PIR, 65 sand-cement screed (build-up ASSUMED - engineer / Part L).												
6B.1	200 compacted hardcore (Type 1), blinded	m3	14.51				**14.51**			£0.00	£0.00	**£0.00**	72.54 m2 x 0.200
6B.2	DPM 1200 gauge (radon-grade if required), lapped / taped, turned up to the ICF and lapped with the DPC	m2	72.54				**72.54**			£0.00	£0.00	**£0.00**	Order guide +10% = 79.8
6B.3	200 RC ground-bearing slab C28/35 on the DPM	m3	14.51				**14.51**			£0.00	£0.00	**£0.00**	72.54 m2 x 0.200
6B.4	Mesh reinforcement A252 (2 layers if the engineer requires), chairs, laps	m2	72.54				**72.54**			£0.00	£0.00	**£0.00**	Order guide +10% = 79.8
6B.5	135 PIR floor insulation on the slab, taped joints, VCL over	m2		72.54			**72.54**			£0.00	£0.00	**£0.00**	Order guide +10% = 79.8
6B.6	25 PIR perimeter edge upstand to the screed against the ICF	m		36.55			**36.55**			£0.00	£0.00	**£0.00**	
6B.7	65 sand-cement screed (or flowing screed) - UFH by M&E if specified	m2		72.54			**72.54**			£0.00	£0.00	**£0.00**	4.72 m3
6C 1F floor (FFL 3,100) - metal-web joists + 22 deck (NRM2 16 - package FLR; joist supplier design)													
	1F floor as modelled (clf_floor_1F.json, 4 bays): PS10 metal-web joists at 400 c/c (top 3,078, underside 2,825) on timber ledgers bolted to the ICF and hangers on timber packers in the steel webs; 22 Egger Protect deck. Joist layout, hangers and fixings by the joist supplier - coordination quantities.												
6C.1	1F metal-web joist floor, supply + fix (joist supplier design)	m2		50.19			**50.19**			£0.00	£0.00	**£0.00**	
6C.2	PS10 metal-web joists (incl. doubled / trimmer joists)	nr		48.00			**48.00**			£0.00	£0.00	**£0.00**	4 doubled, 2 trimmers
6C.3	C24 timber ledger bolted to the ICF (resin / through bolts into the core)	m		13.27			**13.27**			£0.00	£0.00	**£0.00**	4 ledgers, ~18 bolts
6C.4	Joist hangers (ledger / timber packer in the steel web)	nr		96.00			**96.00**			£0.00	£0.00	**£0.00**	42 on ICF ledgers, 54 on steels
6C.5	Strongback (mid-span), fixed to the joist verticals	m		9.67			**9.67**			£0.00	£0.00	**£0.00**	
6C.6	22 Egger Protect P5 deck boards 2,400 x 600, glued T&G, screwed	nr		62.00			**62.00**			£0.00	£0.00	**£0.00**	50.19 m2
6C.7	100 acoustic mineral wool quilt between the joists (Part E E3 internal floor)	m2		50.19			**50.19**			£0.00	£0.00	**£0.00**	
6D 2F floor (FFL 5,800) - metal-web joists + 22 deck (NRM2 16 - package FLR; joist supplier design)													
	2F floor as modelled (clf_floor_2F.json, 3 bays): PS10 metal-web joists at 400 c/c (top 5,778, underside 5,525) on timber ledgers bolted to the ICF and hangers on timber packers in the steel webs; 22 Egger Protect deck. Joist layout, hangers and fixings by the joist supplier - coordination quantities.												
6D.1	2F metal-web joist floor, supply + fix (joist supplier design)	m2			48.37		**48.37**			£0.00	£0.00	**£0.00**	

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
6D.2	PS10 metal-web joists (incl. doubled / trimmer joists)	nr			44.00		**44.00**			£0.00	£0.00	**£0.00**	4 doubled, 2 trimmers
6D.3	C24 timber ledger bolted to the ICF (resin / through bolts into the core)	m			18.48		**18.48**			£0.00	£0.00	**£0.00**	4 ledgers, ~23 bolts
6D.4	Joist hangers (ledger / timber packer in the steel web)	nr			88.00		**88.00**			£0.00	£0.00	**£0.00**	54 on ICF ledgers, 34 on steels
6D.5	Strongback (mid-span), fixed to the joist verticals	m			9.67		**9.67**			£0.00	£0.00	**£0.00**	
6D.6	22 Egger Protect P5 deck boards 2,400 x 600, glued T&G, screwed	nr			57.00		**57.00**			£0.00	£0.00	**£0.00**	48.37 m2
6D.7	100 acoustic mineral wool quilt between the joists (Part E E3 internal floor)	m2			48.37		**48.37**			£0.00	£0.00	**£0.00**	
6E	**Steels and the oriel corbel (NRM2 14 - package STR; ENGINEER - INDICATIVE, sections not designed)**												
	Indicative steels (clf_steel.json, UB 356 x 171 x 51 S355 - engineer to design): SB1 under the 1F main right wall line, SB2 under the 1F main left wall over the GF open plan, SB3 over the porch door, SB4 under the 2F bed 4 stub; bearings in the ICF core (pockets formed at the pour) or on padstones. The oriel is carried on a corbel / steel by the engineer.												
6E.1	SB1 UB 356 x 171 x 51 S355 (indicative), 8,679 long, ~443 kg, fire protection (intumescent / boarded) - 1F floor	m		8.68			**8.68**			£0.00	£0.00	**£0.00**	UB 356x171x51 S355 under the 1F main right wall line (hall / porch + open plan below)
6E.2	SB2 UB 356 x 171 x 51 S355 (indicative), 4,144 long, ~211 kg, fire protection (intumescent / boarded) - 1F floor	m		4.14			**4.14**			£0.00	£0.00	**£0.00**	UB 356x171x51 S355 under the 1F main left wall (den / dine open plan below)
6E.3	SB3 UB 356 x 171 x 51 S355 (indicative), 879 long, ~45 kg, fire protection (intumescent / boarded) - 1F floor	m		0.88			**0.88**			£0.00	£0.00	**£0.00**	UB 356x171x51 S355 under the wing front wall over the porch door
6E.4	SB4 UB 356 x 171 x 51 S355 (indicative), 6,450 long, ~329 kg, fire protection (intumescent / boarded) - 2F floor	m			6.45		**6.45**			£0.00	£0.00	**£0.00**	UB 356x171x51 S355 under the 2F bed 4 stub / main right wall line (wing open below)
6E.5	Steel bearings: pocket / padstone in the ICF core (formed BEFORE the pour of the lift below), packs, bolts	nr		6.00	2.00		**8.00**			£0.00	£0.00	**£0.00**	2 per beam
6E.6	Oriel corbel / support under the oriel (RC corbel or steel frame tied into the ICF) - ENGINEER	m3			0.33		**0.33**			£0.00	£0.00	**£0.00**	Modelled corbel block 837 x 1,990 x 200

PACKAGE SUMMARY - Bill 6 Substructure, GF Slab, Metal-Web Joist Floors, Steels & Oriel Corbel (coordination) (package GRW / FLR / STR; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
6A	Substructure (NRM2 5 / 11 - package GRW; by others - engineer; coordination quantities)	£0.00	£0.00	**£0.00**
6B	GF ground-bearing slab (NRM2 11 - package GRW; engineer)	£0.00	£0.00	**£0.00**
6C	1F floor (FFL 3,100) - metal-web joists + 22 deck (NRM2 16 - package FLR; joist supplier design)	£0.00	£0.00	**£0.00**
6D	2F floor (FFL 5,800) - metal-web joists + 22 deck (NRM2 16 - package FLR; joist supplier design)	£0.00	£0.00	**£0.00**
6E	Steels and the oriel corbel (NRM2 14 - package STR; ENGINEER - INDICATIVE, sections not designed)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 6, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 7 - Roofs - Cut Roof Structure, Clay Double Roman Tiles, Rooflights, PV, Rainwater, Insulation & GF Flat Roofs

Cut roofs (main, wing B, oriel), clay double Roman tiles, valleys / abutments to the parapets, rooflights, PV, rainwater, roof insulation and the GF warm flat roofs. [NRM2 16 / 18 / package RFS / RFC]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
7A	**Roof structure - cut roofs C24 @ 400 (NRM2 16 - package RFS; roof designer / engineer)**												
	Three cut roofs at 50 deg as modelled (struct_Main / struct_Wing / struct_Oriel): MAIN roof between the two parapet gables (eaves walls 6,858, ridge ~10.05 m), wing B cross gable (eaves 5,029, south gable, ridge ~9.24 m) and the oriel dormer (ridge ~8.68 m); rafters on wall plates on the ICF, ceiling ties / collars at ~7,950 (2F rooms in the roof), lay boards in the valleys. Eaves 300 beyond the outer face (oriel 150); no verge at the parapet gables. Sizes / connections by the roof designer.												
7A.1	Common rafters C24 (main + wing + oriel), birdsmouthed on the wall plates	nr				66.00	**66.00**			£0.00	£0.00	**£0.00**	Main 52, Wing 10, Oriel 4
7A.2	Rafter timber C24 - length estimate from the slope area at 400 c/c	m				260.46	**260.46**			£0.00	£0.00	**£0.00**	Order guide +10% = 286.5; estimate
7A.3	Ceiling ties / collars C24 (main collars at the 2F ceiling; wing / oriel ties)	nr				10.00	**10.00**			£0.00	£0.00	**£0.00**	Main 0, Wing 8, Oriel 2
7A.4	Ridge boards (main + wing + oriel)	m				15.50	**15.50**			£0.00	£0.00	**£0.00**	main 9.67 / wing 3.61 / oriel 2.22
7A.5	Purlins / binders (wing B + oriel) - roof designer	nr				4.00	**4.00**			£0.00	£0.00	**£0.00**	
7A.6	Valley lay boards / valley rafters at the wing and oriel cross gables	m				12.17	**12.17**			£0.00	£0.00	**£0.00**	wing B cross gable x 2 7.94, oriel cross gable x 2 4.23
7A.7	100 x 50 C24 wall plates bedded on the ICF (anchor bolts / straps into the core)	m				19.62	**19.62**			£0.00	£0.00	**£0.00**	main left eaves wall (less the oriel) 8.39, main right eaves wall pieces (front + rear) 6.02, wing B front + rear eaves walls 3.54, oriel cheeks 1.67
7A.8	Holding-down / restraint straps (plates to the ICF; gable restraint straps at 2 m)	nr				18.00	**18.00**			£0.00	£0.00	**£0.00**	Estimate
7A.9	Trim rafters for the rooflights (doubled rafters + trimmers each side)	nr				3.00	**3.00**			£0.00	£0.00	**£0.00**	One per rooflight
7B	**Roof coverings, eaves, rainwater and abutments (NRM2 18 / 33 - package RFC)**												
	Slope area = plan at the fascia line x 1.556 (all planes 50 deg; main eaves 300 beyond the outer faces, stopping at the parapet gables). Covering per the elevations legend (4): DARK RED CLAY DOUBLE ROMAN TILES. Rainwater per legend (7): painted cast iron / cast aluminium, downpipes clipped to the walls with swan necks at the eaves.												
7B.1	Dark red clay double Roman tiles on 25 x 50 battens + breathable membrane, nailed / clipped per BS 5534 (main + wing + oriel)	m2				104.18	**104.18**			£0.00	£0.00	**£0.00**	Order guide +10% = 114.6; plan 66.97 m2
7B.2	25 x 50 treated battens at ~340 gauge (tile manufacturer)	m				306.42	**306.42**			£0.00	£0.00	**£0.00**	Order guide +10% = 337.1
7B.3	Clay half-round ridge, dry-fix ridge system with ventilation	m				15.50	**15.50**			£0.00	£0.00	**£0.00**	Order guide +10% = 17.0
7B.4	Valleys: Code 5 lead (or GRP) on valley boards, tile cuts	m				12.17	**12.17**			£0.00	£0.00	**£0.00**	Order guide +10% = 13.4
7B.5	Eaves: fascia, ventilated soffit, eaves carrier / tray, insect mesh	m				19.99	**19.99**			£0.00	£0.00	**£0.00**	main west (Percival Rd) less the oriel 8.09, main east less the wing B cross gable 6.09, wing B front + rear 3.54, oriel cheeks x 2 2.27
7B.6	Verges: bedded / dry verge with undercloak and bargeboard (wing B south gable, oriel gable)	m				15.01	**15.01**			£0.00	£0.00	**£0.00**	wing B south gable (2 rakes) 11.45, oriel dormer gable (2 rakes) 3.56
7B.7	Raked abutment to the parapet gables: lead soakers + stepped cover flashing into the stone	m				17.61	**17.61**			£0.00	£0.00	**£0.00**	4 rakes inside the front + rear parapets
7B.8	Abutments where the wing B / porch roofs meet the main right wall (lead flashings / soakers into the stone)	m				6.02	**6.02**			£0.00	£0.00	**£0.00**	Main right wall pieces above the wing roof
7B.9	Half-round gutters (cast aluminium / cast iron, painted), brackets, outlets, stop ends	m				19.99	**19.99**			£0.00	£0.00	**£0.00**	Order guide +10% = 22.0
7B.10	Downpipes ~9 nr, clipped to the walls (fixings into the ICF webs through the stone joints), swan necks, shoes / connections to the drainage - PROVISIONAL positions	m				48.12	**48.12**			£0.00	£0.00	**£0.00**	main 4 (eaves 6,858), wing 2, one per GF flat roof

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
7B.11	Conservation-style rooflights with flashing kits and blinds (2F rooms, as drawn on the roof plan)	nr				3.00	**3.00**			£0.00	£0.00	**£0.00**	Roof plan PA112
7B.12	Solar PV array on the main east slope (in-roof / on-roof mounting, flashing, inverter, cabling) - by the M&E / PV installer	item				1.00	**1.00**			£0.00	£0.00	**£0.00**	PROVISIONAL - roof plan PA112
7C Roof insulation and VCL (NRM2 18 / 28 - package RFC)													
	WARM pitched roof over the 2F rooms ASSUMED: insulation between + under the rafters from the knee walls to the collar ceiling, VCL on the warm side (42.7 m2 on the slope incl. wing B and the oriel); cold loft over the main collar ceiling (24.0 m2) with quilt on the collar ceiling; the wing B strips over the 1F (2.9 m2) quilted at ceiling level. U-values to Part L.												
7C.1	PIR between the rafters + insulated plasterboard / PIR under the rafters (to Part L), measured on the slope	m2				42.75	**42.75**			£0.00	£0.00	**£0.00**	Order guide +10% = 47.0
7C.2	Mineral wool quilt 300 (100 between + 200 cross-laid) over the collar ceiling and the wing strips	m2				26.93	**26.93**			£0.00	£0.00	**£0.00**	Order guide +10% = 29.6
7C.3	Vapour control layer, taped laps, sealed at the ICF / penetrations	m2				69.68	**69.68**			£0.00	£0.00	**£0.00**	Order guide +10% = 76.6
7C.4	Eaves ventilation / rafter trays to keep the airway over the insulation	m				19.99	**19.99**			£0.00	£0.00	**£0.00**	
7D GF warm flat roofs (NRM2 18 - package RFC)													
	Three warm flat roofs over the single-storey GF parts (CL_flat.json / flat_roofs.json): joists 2,730-2,950, 18 OSB deck, 120 PIR, single-ply membrane to 3,093, inside the ICF parapets (coping in Bill 1). The bay roof is below the stone balustrade (balcony access TBC - architect).												
7D.1	Warm flat roof complete: C24 joists 47 x 220 @ 400 (to falls), 18 OSB3 deck, VCL, 120 PIR, single-ply membrane	m2		14.98			**14.98**			£0.00	£0.00	**£0.00**	FR1 GF wrap (den / WC + utility) 11.25, FR2 porch 2.57, FR3 bay 1.16
7D.2	Flat-roof joists 47 x 220 C24, hangers / ledger on the ICF	nr		28.00			**28.00**			£0.00	£0.00	**£0.00**	FR1 16, FR2 5, FR3 7
7D.3	Membrane upstands to the ICF parapets / walls (150 min) + termination / cover flashings	m		29.33			**29.33**			£0.00	£0.00	**£0.00**	Order guide +10% = 32.3
7D.4	Roof outlets / hoppers to the downpipes (one per flat roof)	nr		3.00			**3.00**			£0.00	£0.00	**£0.00**	

PACKAGE SUMMARY - Bill 7 Roofs - Cut Roof Structure, Clay Double Roman Tiles, Rooflights, PV, Rainwater, Insulation & GF Flat Roofs (package RFS / RFC; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
7A	Roof structure - cut roofs C24 @ 400 (NRM2 16 - package RFS; roof designer / engineer)	£0.00	£0.00	**£0.00**
7B	Roof coverings, eaves, rainwater and abutments (NRM2 18 / 33 - package RFC)	£0.00	£0.00	**£0.00**
7C	Roof insulation and VCL (NRM2 18 / 28 - package RFC)	£0.00	£0.00	**£0.00**
7D	GF warm flat roofs (NRM2 18 - package RFC)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 7, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Bill 8 - Opening Schedule - Windows & External Doors (one line per opening, incl. accessories), Guarding

19 openings from the BuildEase window fit: 16 timber windows, 3 external doors / screen, each with its accessories; guarding and security. [NRM2 25 / package WIN]

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		**1**	**1**	**1**	**1**	**4**						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
8A	**Opening schedule - windows and external doors, one line per opening incl. accessories (NRM2 25 - package WIN; window / door supplier)**												
	From the BuildEase window fit (clw_fit.json, 19 items) and the spec openings: structural opening (so) per opening. Elevations legend (5): TIMBER windows and doors (the fit models a generic alu-clad casement - product, glazing bars and the stone mullion of L2-W01 by the supplier); (6) the PPC aluminium glazed screen to the garden. Each line includes: the frame, double glazing (obscure where noted), fixing straps into the ICF, INTERNAL illbruck ME110 airtightness tape round the frame, the stone / render reveal seal (Bill 1D.3), trickle vents to the windows (Approved Document F) and the frame-to-cill bedding. Frames tight to the back of the outer EPS.												
8A.1	L1-W01: Timber double-glazed casement window, 1 light, 392 x 1,641 so - den rear, tall narrow (rear elevation 0.43 wide); trickle vent; ME110 tape 4.07 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 670
8A.2	L1-D01: PPC aluminium 3-panel sliding glazed screen, low threshold (elevations legend 6), 3,539 x 2,311 so - dine / cook 3-panel PPC aluminium sliding screen to the patio; ; ME110 tape 11.70 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 0
8A.3	L1-W02: Timber double-glazed casement window, 1 light, 544 x 1,311 so - kitchen rear (wing B); trickle vent; ME110 tape 3.71 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	render wall; sill 1,000
8A.4	L1-D02: External door (timber per the elevations legend 5 / composite), multi-point lock, PAS 24, 981 x 2,631 so - main entrance (porch front), 980 centred - drawn frame 384.9-418.3 leaves 180 / 40 mm piers; ; ME110 tape 7.22 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 0
8A.5	L1-D03: External door (timber per the elevations legend 5 / composite), multi-point lock, PAS 24, 815 x 2,631 so - service entrance to WC / utility + ASHP access; ; ME110 tape 6.89 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 0
8A.6	L1-W03: Timber double-glazed casement window, 2 lights, 1,316 x 2,071 so - bay front (sitting room); trickle vent; ME110 tape 6.77 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 560
8A.7	L2-W01: Timber double-glazed casement window, 3 lights, 2,054 x 1,681 so - bedroom 1 rear, 2-light stone-mullioned (drawn as a pair); sill 610 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 7.47 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	rubble wall; sill 3,710
8A.8	L2-W02: Timber double-glazed casement window, 1 light, 558 x 1,171 so - en-suite rear (wing B); OBSCURE glass, sill 650 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 3.46 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	render wall; sill 3,750
8A.9	L2-W03: Timber double-glazed casement window, 3 lights, 2,033 x 1,621 so - bedroom 2 front, over the bay; sill 690 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 7.31 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	rubble wall; sill 3,790
8A.10	L2-W04: Timber double-glazed casement window, 1 light, 509 x 1,151 so - bathroom front (wing B, rendered); OBSCURE glass, sill 700 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 3.32 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	render wall; sill 3,800
8A.11	L2-W05: Timber double-glazed casement window, 1 light, 717 x 1,151 so - stair / landing, Percival Road (upper); sill 650 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 3.74 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	rubble wall; sill 3,750

Ref	Description	Unit	FB foundation	L1 GF	L2 1F + oriel	L3 2F + roofs	Site total qty	Supply rate £	Install rate £	Supply £	Install £	Line total £	Notes
	One building - quantity per level (Site total = sum of the levels)		1	1	1	1	4						Levels: FB = foundation: 2 courses 6in XR35 -914.4 to 0 on the strip footing (by others); Brick Ledge top course on the external walls; L1 = ground floor: 7 courses 0 to 3,200.4 (GF ceiling 2,825; single-storey parapets to 3,200); GF flat roofs; L2 = first floor: 6 courses 3,200.4 to 5,943.6 (1F FFL 3,100, ceiling 5,525); wing B eaves 5,029; oriel from 4,343; L3 = second floor in the roof (FFL 5,800):
8A.12	L2-W06: Timber double-glazed casement window, 1 light, 713 x 1,151 so - stair / landing, Percival Road (lower); sill 650 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 3.73 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	rubble wall; sill 3,750
8A.13	L2-W07: Timber double-glazed casement window, 1 light, 671 x 1,101 so - bathroom south (obscured); OBSCURE glass, sill 700 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 3.54 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	render wall; sill 3,800
8A.14	L3-W01: Timber double-glazed casement window, 2 lights, 1,168 x 1,881 so - bedroom 3 front gable; sill 740 above FFL - guarding / restrictor (8B.1), trickle vent; ME110 tape 6.10 m	nr				1.00	**1.00**			£0.00	£0.00	**£0.00**	rubble wall; sill 6,540
8A.15	L3-W02: Timber double-glazed casement window, 2 lights, 1,168 x 1,581 so - bedroom 4 rear gable; trickle vent; ME110 tape 5.50 m	nr				1.00	**1.00**			£0.00	£0.00	**£0.00**	rubble wall; sill 6,620
8A.16	L2-W08: Timber double-glazed casement window, 1 light, 1,101 x 1,254 so - oriel front window (split at the 1F / 2F level joint, glazing continuous); trickle vent; ME110 tape 4.71 m	nr			1.00		**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 4,690
8A.17	L3-W04: Timber double-glazed casement window, 1 light, 471 x 561 so - wing B south gable, high level, obscured (shower room); OBSCURE glass, trickle vent; ME110 tape 2.06 m	nr				1.00	**1.00**			£0.00	£0.00	**£0.00**	render wall; sill 7,660
8A.18	L1-W04: Timber double-glazed casement window, 1 light, 851 x 2,071 so - bay side window (850 centred on the side); trickle vent; ME110 tape 5.84 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 560
8A.19	L1-W05: Timber double-glazed casement window, 1 light, 851 x 2,071 so - bay side window (850 centred on the side); trickle vent; ME110 tape 5.84 m	nr		1.00			**1.00**			£0.00	£0.00	**£0.00**	ashlar wall; sill 560
8A.W	**Windows - total structural opening area (information)**	**m2**		**7.61**	**11.75**	**4.31**	**23.67**					*not priced*	
8A.T	**illbruck ME110 internal airtightness tape round all frames (included in the lines above - information)**	**m**		**52.05**	**37.27**	**13.66**	**102.99**					*not priced*	
8B Guarding, security and items not modelled (PROVISIONAL)													
8B.1	Guarding to the upper-floor windows with a sill below 800 above the floor (ADK K2 / Part K: fixed laminated lower pane, guard rail or restrictors with child-safe release + escape windows per ADB)	nr			7.00	1.00	**8.00**			£0.00	£0.00	**£0.00**	L2-W01, L2-W02, L2-W03, L2-W04, L2-W05, L2-W06, L2-W07, L3-W01
8B.2	Approved Document Q security: PAS 24 doorsets and easily accessible windows (GF + the windows by the flat roofs)	nr		8.00			**8.00**			£0.00	£0.00	**£0.00**	Supplier certification
8B.3	Background ventilation / MVHR strategy (Approved Document F) and overheating check (Approved Document O) - M&E / window supplier	item								£0.00	£0.00	**£0.00**	Lump sum - the rate entered is the amount. PROVISIONAL

PACKAGE SUMMARY - Bill 8 Opening Schedule - Windows & External Doors (one line per opening, incl. accessories), Guarding (package WIN; amounts by others, excl. VAT)

Section	Description	Supply £	Install £	Total £
8A	Opening schedule - windows and external doors, one line per opening incl. accessories (NRM2 25 - package WIN; window / door supplier)	£0.00	£0.00	**£0.00**
8B	Guarding, security and items not modelled (PROVISIONAL)	£0.00	£0.00	**£0.00**
	PACKAGE TOTAL - Bill 8, carried to the Cover overview	**£0.00**	**£0.00**	**£0.00**

Pale-yellow cells are the only inputs (Supply rate, Install rate). Amounts, subtotals and totals are formulas; the sheet is protected without a password (Review > Unprotect Sheet). Amounts exclude VAT and are NOT part of the Nudura ICF price.

Schedule A - Areas: Facades by Finish, Lining Zone

Facade faces = ICF outer-face lines x level heights / cut planes less openings; ICF f

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Level	Item	Source	Length m	Gross m2 / width m	Net area m2
FB	rear (garden) W01 - ashlar limestone	spec chains x heights	7.81	1.17	1.17
FB	rear (garden) W01 (wing B) - render (wing B)	spec chains x heights	1.77	0.27	0.27
FB	wing B / porch east W02 (wing B) - render (wing B)	spec chains x heights	6.76	1.01	1.01
FB	wing B / porch east W02 (porch side) - ashlar limestone	spec chains x heights	2.17	0.33	0.33
FB	porch front W03 - ashlar limestone	spec chains x heights	1.77	0.27	0.27
FB	main right return W04 - coursed rubble stone	spec chains x heights	1.28	0.19	0.19
FB	bay side W05 - ashlar limestone	spec chains x heights	1.68	0.25	0.25
FB	bay front W06 - ashlar limestone	spec chains x heights	2.30	0.35	0.35
FB	bay side W07 - ashlar limestone	spec chains x heights	1.68	0.25	0.25
FB	main left (Percival Rd) W08 - coursed rubble stone	spec chains x heights	3.41	0.51	0.51
FB	GF wrap front W09 - ashlar limestone	spec chains x heights	1.67	0.25	0.25
FB	GF wrap left W10 (retained boundary wall) - retained boundary wall (no facing)	spec chains x heights	6.89	1.03	1.03
L1	rear (garden) W01 - ashlar limestone (less L1-W01, L1-D01)	spec chains x heights	7.81	25.00	16.18
L1	rear (garden) W01 (wing B) - render (wing B) (less L1-W02)	spec chains x heights	1.77	5.66	4.94
L1	wing B / porch east W02 (wing B) - render (wing B)	spec chains x heights	6.76	21.64	21.64
L1	wing B / porch east W02 (porch side) - ashlar limestone	spec chains x heights	2.17	6.95	6.95
L1	porch front W03 - ashlar limestone (less L1-D02)	spec chains x heights	1.77	5.66	3.08
L1	main right return W04 - coursed rubble stone	spec chains x heights	1.28	4.09	4.09
L1	bay side W05 - ashlar limestone (less L1-W05)	spec chains x heights	1.68	5.37	3.61
L1	bay front W06 - ashlar limestone (less L1-W03)	spec chains x heights	2.30	7.37	4.64
L1	bay side W07 - ashlar limestone (less L1-W04)	spec chains x heights	1.68	5.37	3.61
L1	main left (Percival Rd) W08 - coursed rubble stone	spec chains x heights	3.41	10.92	10.92
L1	GF wrap front W09 - ashlar limestone (less L1-D03)	spec chains x heights	1.67	5.33	3.19
L1	GF wrap left W10 (retained boundary wall) - retained boundary wall (no facing)	spec chains x heights	6.89	22.04	22.04
L2	wing B rear W01 - render (wing B) (less L2-W02)	spec chains x heights	1.77	3.23	2.58
L2	wing B east W02 - render (wing B) (less L2-W07)	spec chains x heights	6.76	18.12	17.38
L2	wing B front W03 - render (wing B) (less L2-W04)	spec chains x heights	1.77	3.23	2.65
L2	main right (front part) W04 - coursed rubble stone	spec chains x heights	3.62	9.93	9.93
L2	main front W05 - coursed rubble stone (less L2-W03)	spec chains x heights	5.06	13.88	10.59
L2	main left (Percival Rd) W06 - coursed rubble stone (less L2-W05, L2-W06)	spec chains x heights	10.38	25.29	23.65
L2	main rear W07 - coursed rubble stone (less L2-W01)	spec chains x heights	5.06	13.88	10.43
L2	oriel front W09 - ashlar limestone (less L2-W08)	spec chains x heights	1.99	3.18	1.80
L2	oriel cheek W08 - ashlar limestone	spec chains x heights	0.84	1.34	1.34
L2	oriel cheek W10 - ashlar limestone	spec chains x heights	0.84	1.34	1.34
L3	main front parapet gable W02 - coursed rubble stone (less L3-W01)	spec chains x heights	5.06	13.99	11.79

Level	Item	Source	Length m	Gross m2 / width m	Net area m2
L3	main rear parapet gable W04 - coursed rubble stone (less L3-W02)	spec chains x heights	5.06	13.99	12.14
L3	main left eaves wall W03 (less behind the oriel) - coursed rubble stone	spec chains x heights	10.38	7.67	7.67
L3	main right eaves wall front W01 / W11 (above the porch / wing roof) - coursed rubble stone	spec chains x heights	4.10	3.75	3.75
L3	main right eaves wall rear W05 (above the wing roof only) - coursed rubble stone	spec chains x heights	1.91	0.92	0.92
L3	wing B south gable W06 / W07 - render (wing B) (less L3-W04)	spec chains x heights	6.76	9.22	8.96
L3	oriel dormer gable W09 - ashlar limestone	spec chains x heights	1.99	3.91	3.91
L3	oriel cheek W08 - ashlar limestone	spec chains x heights	0.84	1.15	1.15
L3	oriel cheek W10 - ashlar limestone	spec chains x heights	0.84	1.15	1.15
all	TOTAL coursed rubble stone (net of openings)	derived			106.59
all	TOTAL ashlar limestone (net of openings)	derived			54.82
all	TOTAL render (wing B) (net of openings)	derived			59.43
all	TOTAL retained boundary wall (no facing) (net of openings)	derived			23.07
FB	Below-ground outer leaf, Brick Ledge shelf to ground (Bill 1A.3)	derived	32.29		9.92
FB	FB below-ground outer EPS faces (protection, Bill 6A.2)	CL_components.json			31.01
FB	Cross-check: ICF outer EPS faces, external walls (Report Tool, openings net)	CL_components.json			37.10
L1	Cross-check: ICF outer EPS faces, external walls (Report Tool, openings net)	CL_components.json			109.33
L2	Cross-check: ICF outer EPS faces, external walls (Report Tool, openings net)	CL_components.json			88.17
L3	Cross-check: ICF outer EPS faces, external walls (Report Tool, openings net)	CL_components.json			54.52
L1-L3	Lining zone GF: ICF envelope inner faces	CL_components.json			77.90
L1-L3	Lining zone 1F: ICF envelope inner faces	CL_components.json			64.16
L1-L3	Lining zone 2F: ICF envelope inner faces	CL_components.json			40.14
L1-L3	Lining zone LOFT: ICF envelope inner faces	CL_components.json			9.17
L1-L3	Lining zone ORIEL: ICF envelope inner faces	CL_components.json			8.53
L1	Internal ICF load-bearing walls, both faces (GF zone)	CL_components.json	2.97		16.78
FB	GF slab inside the ICF inner faces	clf_slab.json	36.55		72.54
L1	1F metal-web joist floor	clf_floor_1F.json			50.19
L2	2F metal-web joist floor	clf_floor_2F.json			48.37
L1	GF ceilings = 1F floor + GF flat roofs less partitions	derived			62.96
L2	1F ceilings = 2F floor + wing B strips less partitions	derived			49.10
L3	2F rooms in the roof: main section on the slope + collar ceiling	derived	9.67	5.38	52.06
L3	2F wing B room on the slope / oriel on the slope	derived			14.71
L3	Cold loft over the collar ceiling (ASSUMED collar ~8,200)	derived	9.67	2.48	24.03
L1	Building outline GF (ICF outer faces)	CL_spec chains	39.18		86.00
L3	Roof plan at the fascia line (main + wing B + oriel)	outline	19.99		66.97
L3	Roof ON THE SLOPE (plan x 1.556)	derived			104.18
L3	Warm roof insulation on the slope (knee to collar)	derived			42.74
L1	GF flat roof FR1 GF wrap (den / WC + utility)	CL_flat.json	15.95		11.25
L1	GF flat roof FR2 porch	CL_flat.json	6.46		2.57
L1	GF flat roof FR3 bay	CL_flat.json	6.92		1.16

Ground ASSUMED ~150 below GF FFL all round. Finish split read off the PA113 / PA114 elevations. Cross-check rows = Report Tool outer EPS faces.

Schedule B - Openings Schedule (spec openings + BuildEase window fit)

From CL_spec.json (19 ICF openings) and clw_fit.json (19 fitted items). Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Level	Ref	Type	Fit style	W mm	H mm	Sill mm	Area m2	Fit so (W x H)	Wall finish
L1	L1-W01	window	window	392	1640	670	0.64	392 x 1641	ashlar limestone
L1	L1-D01	door	double_door	3538	2310	0	8.17	3539 x 2311	ashlar limestone
L1	L1-W02	window	window	543	1310	1000	0.71	544 x 1311	render
L1	L1-D02	door	composite_door	980	2630	0	2.58	981 x 2631	ashlar limestone
L1	L1-D03	door	composite_door	815	2630	0	2.14	815 x 2631	ashlar limestone
L1	L1-W03	window	window	1316	2070	560	2.72	1316 x 2071	ashlar limestone
L2	L2-W01	window	window	2053	1680	3710	3.45	2054 x 1681	coursed rubble stone
L2	L2-W02	window	window	557	1170	3750	0.65	558 x 1171	render
L2	L2-W03	window	window	2032	1620	3790	3.29	2033 x 1621	coursed rubble stone
L2	L2-W04	window	window	508	1150	3800	0.58	509 x 1151	render
L2	L2-W05	window	window	716	1150	3750	0.82	717 x 1151	coursed rubble stone
L2	L2-W06	window	window	713	1150	3750	0.82	713 x 1151	coursed rubble stone
L2	L2-W07	window	window	670	1100	3800	0.74	671 x 1101	render
L3	L3-W01	window	window	1168	1880	6540	2.20	1168 x 1881	coursed rubble stone
L3	L3-W02	window	window	1168	1580	6620	1.84	1168 x 1581	coursed rubble stone
L2	L2-W08	window	window	1100	1254	4690	1.38	1101 x 1254	ashlar limestone
L3	L3-W04	window	window	470	560	7660	0.26	471 x 561	render

Level	Ref	Type	Fit style	W mm	H mm	Sill mm	Area m2	Fit so (W x H)	Wall finish
L1	L1-W04	window	window	850	2070	560	1.76	851 x 2071	ashlar limestone
L1	L1-W05	window	window	850	2070	560	1.76	851 x 2071	ashlar limestone

Sills are above GF FFL (0). 1F FFL 3,100 / 2F FFL 5,800. "not fitted" / "fit only" rows = the fit and the spec are out of step (re-run the fit).

Schedule C - Key Quantities per Level

Reference only - the bills carry the priced quantities. Not priced.

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Level	ICF outer face m2	ICF inner face m2	External finish m2	Wall linings m2	Ceilings m2	Door leaves nr	Skirting m	Partitions m2
FB	39.82	34.48	4.84	0.00	0.00	0	0.00	0.00
L1	118.84	100.52	82.86	196.87	62.96	5	67.03	52.43
L2	88.17	76.48	81.70	148.17	49.10	5	60.84	44.34
L3	54.52	49.79	51.44	92.77	64.78	3	70.33	28.90
Total	**301.35**	**261.27**	**220.84**	**437.81**	**176.84**	**13.00**	**198.20**	**125.67**

ICF faces from the Report Tool component export (481 forms; inner + outer incl. the internal ICF walls). External finish = stone + render (excl. the retained wall). L3 ceilings = rooms in the roof on the slope.

Schedule D - TLSTF Partition Schedule (GF / 1F as built; 2F ASSUMED from the

From the TLSTF walls / verify / doors / ceiling-noggin reports (04_Logs/build/CL/CLP_*) and CL_partitions.json (2F). Not priced

DISCLAIMER: This information is supplied in good faith for guidance and coordination only. It is not part of the Nudura ICF price and must be checked and verified by the appropriate professional (quantity surveyor, designer, engineer or supplier) before use. Only the Nudura ICF formwork and associated accessories are included in our price. Quantities are measured from the BuildEase quotation model of the O'Leary Goss Architects 3299 PA111 D / PA112 D / PA113 C / PA114 C (planning: plans, roof plan, elevations, 1:100 @ A3); facade areas are measured from the model wall lines x the level heights less the openings (finish split read off the elevations); no allowance for waste is included unless stated. Quantity columns are the model levels FB / L1 (GF) / L2 (1F) / L3 (2F + roofs); the Site total is their sum. Rates and amounts are by others.

Floor	Wall	Length mm	Height mm	Area m2	Build-up	Studs	Members	Door openings (mm)	Head clips
GF	GF-P02	6117	2,825	17.28	cl_int_89_600	14	69	820	12
GF	GF-P03	2117	2,825	5.98	cl_int_89_600	4	24	800	5
GF	GF-P04	2117	2,825	5.98	cl_int_89_600	5	26	1200	6
GF	GF-P05	4350	2,825	12.29	cl_int_89_600	9	47	800	3
GF	GF-P06	2167	2,825	6.12	cl_int_89_600	5	19		7
GF	GF-P01	1690	2,825	4.77	cl_int_89_400	5	19		
1F	1F-P01	6117	2,425	14.83	cl_int_89_400	19	87	800	12
1F	1F-P02	3945	2,425	9.57	cl_int_89_600	9	56	600, 700	10
1F	1F-P03	1768	2,425	4.29	cl_int_89_400	6	23		4
1F	1F-P04	2105	2,425	5.10	cl_int_89_400	7	34	750	8
1F	1F-P05	4350	2,425	10.55	cl_int_89_400	13	61	800	9
2F	2F-P01	2642	~1,954	5.16	ASSUMED 89 @ 600	6	-		-
2F	2F-P02	1220	~2,150	2.62	ASSUMED 89 @ 600	4	-		-
2F	2F-P03	1143	~2,079	2.38	ASSUMED 89 @ 600	3	-	800	-
2F	2F-P04	2735	~1,711	4.68	ASSUMED 89 @ 600	6	-	700	-
2F	2F-P05	2332	~1,245	2.90	ASSUMED 89 @ 600	5	-		-
2F	2F-P06	2332	~1,218	2.84	ASSUMED 89 @ 600	5	-		-
2F	2F-P07	4350	~1,912	8.32	ASSUMED 89 @ 600	9	-	800	-

GF 6 walls 18.6 m / 1F 5 walls 18.3 m / 2F 7 walls 16.8 m = 53.6 m, 12 door openings (2F assumed - not modelled). GF to the 1F joist underside; 1F to the 2F joist underside; 2F mean height under the assumed rafter soffit / collar ceiling.